STATE OF VERMONT
AGENCY OF TRANSPORTATION

COMPOSITE QUANTITY SHEET 1

VAOT Metric

FAYSTON-WAITSFIELD STP 2406(I)S			WAITSFIELD - MORETOWN STP 2227(I)S					APPROXIMATE SUMMARY OF QUANTITIES		
FULL E & C	BRIDGE	ROADWAY	FULL E & C	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
-	-	4	-	-	4	8	EA	THINNING AND TRIMMING (FOR SIGNS)	201.31	
-	-	-	-	-	10	10	m^3	COMMON EXCAVATION	203.15	
-	-	210	-	-	2,000	2,210	m^3	EARTH BORROW	203.30	
-	-	0.2	-	-	0.8	1	m^3	TRENCH EXCAVATION OF EARTH (N.A.B.I.)	204.20	
-	-	20,300	-	-	47,500	67,800	m^2	COLD PLANING - BITUMINOUS PAVEMENT	210.10	
-	-	1,500	-	-	8,350	9,850	t	SUBBASE OF CRUSHED GRAVEL (FINE GRADED) (MOD.)	301.28	
-	-	-	-	-	54,500	54,500	m^2	RECLAIMED STABILIZED BASE	310.20	
-	-	590	-	-	2,900	3,490	t	AGGREGATE SHOULDERS (MOD.)	402.12	
-	-	2,500	-	-	14,000	16,500	kg	EMULSIFIED ASPHALT	404.65	
-	-	0.2	-	-	0.8	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	
-	-	2,000	-	-	21,000	23,000	t	SUPERPAVE BITUMINOUS CONC. PAVE. (PG 58-34)	490.30	
-	1	-	-	-	-	1	m^3	CONCRETE - CLASS A	501.22	
-	100	-	-	-	-	100	KG	REINFORCING STEEL	507.15	
-	36	-	-	20	-	56	m	BRIDGE EXPANSION JOINT (ASPHALTIC PLUG)	516.10	
-	-	-	-	70	-	70	m	REMOVAL OF EXISTING RAILING	525.10	
-	-	-	-	-	50	50	m	375mm CSP 1.63mm (68mm x 12mm)	601.0010	
-	-	-	-	-	50	50	m	450mm CSP 1.63mm (68mm x 12mm)	601.0015	
-	-	-	-	-	100	100	m	450mm CPEP	601.0915	
-	-	-	-	-	3	3	EA	375mm CSPES 1.63mm (68mm x 12mm)	601.6010	
-	-	-	-	-	3	3	EA	450mm CSPES 1.63mm (68mm x 12mm)	601.6015	
-	-	-	-	-	5	5	EA	450mm CPEPES	601.7015	
-	-	3	-	-	8	11	EA	REHABING OF DI, CB OR MH, CLASS I	604.412	
-	-	-	-	-	100	100	m	150mm UNDERDRAIN	605.10	
-	-	50	-	-	100	150	HR	POWER GRADER RENTAL	608.15	
-	-	90	-	-	350	440	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	
-	-	30	-	-	50	80	HR	POWER BROOM RENTAL	608.30	
-	-	10	-	-	30	40	HR	POWER BROOM RENTAL, TYPE II	608.31	
-	-	180	-	-	700	880	HR	TRUCK RENTAL	608.37	
-	-	-	-	-	10	10	t	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	
-	-	10	-	-	170	180	m^3	STONE FILL, TYPE I	613.10	
-	-	5	-	-	10	15	t	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	
-	-	-	-	-	1	1	EA	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	
-	-	-	-	-	1	1	EA	RELOCATE MAILBOX, MULTIPLE SUPPORT	617.12	
-	-	38	-	-	35	73	EA	YIELDING MARKER POSTS	619.17	
-	-	450	-	-	-	450	m	STEEL BEAM GUARDRAIL (GALVANIZED)	621.20	
-	-	-	-	-	1,600	1,600	m	BOX BEAM GUARDRAIL (GALVANIZED)	621.30	
-	-	-	-	170	-	170	m	BOX BEAM GUARDRAIL (GALVANIZED) (MOD. 3)	621.30	
-	-	220	-	-	800	1,020	m	BOX BEAM GUARDRAIL (GALVANIZED)(2.1 m POSTS)	621.30	
-	-	3	-	-	-	3	EA	MANUFACTURED TERMINAL SECTION (FLARED)	621.505	
-	-	4	-	-	-	4	EA	TERMINAL CONNECTOR FOR STEEL BEAM GUARDRAIL	621.53	
-	-	3	-	-	-	3	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	
-	-	520	-	-	2,325	2,845	m	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	
-	-	-	-	-	10	10	EA	REMOVAL AND DISPOSAL OF GUIDE POSTS	621.81	

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS

NOTE: REFER TO SHEETS 8 AND 9 FOR THE INDIVIDUAL QUANTITY SHEETS FOR FAYSTON - WAITSFIELD STP 2406(1)S AND SHEETS 27 AND 28 FOR THE WAITSFIELD - MORETOWN STP 2227(1)S PROJECT.

STATIONS		PAVEMENT WIDTHS			EQUATIONS				REMARKS
FROM	TO				+	-			
TOTALS									

pave/00b058/00b058.dgn
00b058qscl.i 23-MAY-2008 12:54

PROJECT NAME FAYSTON - WAITSFIELD STP 2406(I)S AND
PROJECT NUMBER WAITSFIELD - MORETOWN STP 2227(I)S