

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES

TOTALS

DESCRIPTIONS

DETAILED SUMMARY OF QUANTITIES

SUMMARY OF ESTIMATED QUANTITIES										TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
NON-PARTICIPATION					PARTICIPATION					NON-PARTICIPATION	PARTICIPATION	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS
EROSION CONTROL	ROADWAY	FULL C.E. ITEMS	EROSION CONTROL	ROADWAY	RETAINING WALL	EROSION CONTROL	ROADWAY	RETAINING WALL										
60										60		CY	STONE FILL, TYPE II	613.11				
				50							50	LF	VERTICAL GRANITE CURB - 964.6 LF PER STATIONING	616.21				
				1040							1040	LF	REMOVING AND RESETTING CURB	616.40				
				500							500	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 NCH	618.10				
	380			735						380	735	LF	SNOW FENCE (MOD. PDF)	620.70				
				3							3	EACH	ENERGY ABSORPTION ATTENUATOR (SAND FILLED BARRELS)	621.56				
				270							270	LF	REMOVING AND RESET GUARD RAIL	621.75				
				620							620	LF	TEMPORARY TRAFFIC BARRIER	621.90				
				80							80	HR	UNIFORMED TRAFFIC OFFICERS	630.10				
				200							200	HR	FLAGGERS	630.15				
			1								1	LS	FIELD OFFICE-ENGINEERS	631.10				
			1								1	LS	TESTING EQUIPMENT - CONCRETE	631.16				
			1								1	LS	TESTING EQUIPMENT - BITUMINOUS (MOD.)	631.17				
			1								1	LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25				
				1							1	LS	MOBILIZATION	635.10				
				1							1	LS	TRAFFIC CONTROL	641.10				
				1530							1530	LF	DURABLE 4" WHITE LINE	646.40				
				1440							1440	LF	DURABLE 4" YELLOW LINE	646.41				
				13							13	LF	DURABLE 24" STOP BAR	646.46				
				8							8	EACH	DURABLE LETTER OR SYMBOL	646.50				
				50							50	LF	DURABLE CROSSWALK MARKING W/DIAGONAL LINES	646.51				
				1400							1400	LF	TEMPORARY 4" WHITE LINE	646.60				
				1340							1340	LF	TEMPORARY 4" YELLOW LINE	646.61				
				84							84	LF	TEMPORARY CROSSWALK MARKING W/DIAGONAL LINES	646.71				
				900							900	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85				
	160										160	SY	GEOTEXTILE UNDER STONE FILL	649.31				
	950						410				950	410	SY	GEOTEXTILE FOR UNDERDRAIN TRENCH LINING	649.41			
280						150					280	150	SY	GEOTEXTILE FOR SILT FENCE	649.51			
25						6					25	6	LB	SEED	651.15			
25						6					25	6	LB	SEED-WINTER RYE	651.17			
160						40					160	40	LB	FERTILIZER	651.18			
0.7						0.15					0.7	0.15	TON	AGRICULTURAL LIMESTONE	651.20			
0.7						0.15					0.7	0.15	TON	HAY MULCH	651.25			
40						20					40	20	CY	TOPSOIL	651.35			
0.5						0.5					0.5	0.5	LS	EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.10			
20						20					20	20	HR	MONITORING EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.20			
0.5						0.5					0.5	0.5	LU	MAINTENANCE OF EROSION PREVENTION & SEDIMENT CONTROL PLAN (N.A.B.I.)	652.30			
1300											1300		SY	EROSION MATTING	654.10			
							14					14	LF	FLANGED CHANNEL SIGN POST	675.301			
							6					6	EACH	REMOVING SIGNS	675.50			
							6					6	EACH	ERECTING SALVAGED SIGNS	675.60			
							4					4	EACH	SETTING SALVAGED POSTS	675.61			

PROJECT NAME: **SPRINGFIELD**
 PROJECT NUMBER: **STP 016-2 (10)S**
 FILE NAME: \00B124\structures\sb124qty.xls PLOT DATE: 07/12/2004
 PROJECT MANAGER: R. R. WHITCOMB DRAWN BY: G. ROY
 DESIGNED BY: G. ROY CHECKED BY: R. R. WHITCOMB
 QUANTITY SHEET #2 SHEET 5 OF 72