QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

			VT 78 ROBIN HOOD DR	EROSION CONTROL	FULL E&C	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						2100	2100	CY	COMMON EXCAVATION	203.15	34
						10	10	CY	EARTH BORROW	203.30	EST.
						510	510	CY	SAND BORROW	203.31	2
						3000	3000	SY	FINE GRADING-SUBGRADE	203.40	20
						50	50	CY	TRENCH EXCAVATION OF EARTH	204.20	EST.
						3700	3700	SY	COLD PLANING-BIT. PAVEMENT	210.10	33
						2150	2150	CY	SUBBASE DENSE GRADED CRUSHED STONE	301.35	17
						130	130	CY	AGGREGATE SURFACE COURSE	401.10	7
						7.5	7.5	CWT	EMULSIFIED ASPHALT	404.65	
						1260	1260	TON	BITUMINOUS CONCRETE PAVEMENT (PG 58-28)	406.25	35
						50	50	LF	RELAYING PIPE CULVERTS	601.99	EST.
						1	1	EA	CHANGE ELEVATION OF DI, CB, OR MH	604.40	EST.
						1	1	EA	REHABING DI,CB OR MH CLASS I	604.412	EST.
						1	1	EA	CHANGING ELEVATION OF SEWER MANHOLE	604.42	EST.
						6	6	HR	BULLDOZER RENTAL, TYPE I	608.10	EST.
						6	6	HR	POWER GRADER RENTAL	608.15	EST.
						6	6	HR	ALL PURP. EXCAVATOR RENTAL, TYPE I	608.25	EST.
						6	6	HR	POWER BROOM RENTAL	608.30	EST.
						6	6	HR	TRUCK RENTAL	608.37	EST.
						154	154	M/GAL	DUST CONTROL W/WATER	609.10	EST.
						1	1	TON	DUST AND ICE CONTROL W/CALC. CHLORIDE	609.15	EST.
				50			50	CY	STONE FILL TYPE I(MOD-CHECK DAM)	613.10	EST.
				50			50	CY	STONE FILL TYPE I(MOD CONSTRUCTION ENTRANCE)	613.10	EST.
				50			50	CY	STONE FILL TYPE I(MOD - INLET PROTECTION)	613.10	EST.
						185	185	LF	CAST-IN-PLACE CONC. CURB, TYPE B (MOD)	616.28	-
						3	3	EA	RELOCATE MAIL BOX, SINGLE SUPPORT	617.10	
						15	15	SY	PORTLAND CEMENT CONC. SIDEWALK 5'' (MOD)	618.10	1
						10	10	SY	DETECTABLE WARNING SURFACE	618.30	2
						1	1	EA	ADJUST ELEV. OF VALVE BOX	629.20	-
						150	150	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
						150	150	HR	FLAGGERS	630.15	EST.
					1		1	LS	FIELD OFFICE - ENGINEER	631.10	
					1		1	LS	TESTING EQUIPMENT - CONCRETE	631.16	-
					1		1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	-
					1		1	LU	FIELD OFFICE - TELEPHONE (NOT A BID ITEM)	631.25	
						1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	EST.
						1	1	LS	TRAFFIC CONTROL	641.10	EST.
						3050	3050	LF	DURABLE 4'' WHITE LINE (THERMOPLASTIC)	646.40	8
						3130	3130	LF	DURABLE 4'' YELLOW LINE (THERMOPLASTIC)	646.41	8

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: SWANTON
PROJECT NUMBER: STPG ST 036-1(11)

FILE NAME: PW:\TRAFFIC DES.\00bi50\tbi50tit.dgn
PROJECT LEADER: B. NYQUIST
DESIGNED BY: TRAFFIC DESIGN
tbi05q01.i

PLOT DATE: 26-APR-2006
DRAWN BY: TRAFFIC DESIGN
CHECKED BY: TRAFFIC DESIGN
SHEET 4 OF 45