# QUANTITY SHEET

**STATE OF VERMONT**
**AGENCY OF TRANSPORTATION**

## SUMMARY OF ESTIMATED QUANTITIES

| | | | VT 78 ROBIN HOOD DR | EROSION CONTROL | FULL E&C | ROADWAY | QUANTITIES GRAND TOTAL | UNIT | ITEMS | ITEM NO. | ROUNDING |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | 1000 | 1000 | LF | DURABLE 8'' YELLOW LINE (THERMOPLASTIC) | 646.43 | 11 |
| | | | | | | 115 | 115 | LF | DURABLE 24'' STOP BAR (THERMOPLASTIC) | 646.46 | - |
| | | | | | | 15 | 15 | EA | DUR. LETTER OR SYMBOL (THERMOPLASTIC) | 646.50 | |
| | | | | | | 560 | 560 | LF | DUR. CROSSWALK MKG W/DIAG LINES (THERMOPLASTIC) (MOD-BLOCK TYPE) | 646.51 | |
| | | | | | | 3050 | 3050 | LF | TEMPORARY 4'' WHITE LINE (PAINT) | 646.60 | 8 |
| | | | | | | 3130 | 3130 | LF | TEMPORARY 4'' YELLOW LINE (PAINT) | 646.61 | 8 |
| | | | | | | 1000 | 1000 | LF | TEMPORARY 8'' YELLOW LINE (PAINT) | 646.63 | 11 |
| | | | | | | 115 | 115 | LF | TEMPORARY 24'' STOP BAR (PAINT) | 646.66 | |
| | | | | | | 15 | 15 | EA | TEMPORARY LETTER OR SYMBOL (PAINT) | 646.70 | - |
| | | | | | | 560 | 560 | LF | TEMP. CROSSWALK MKG W/DIAG LINES (PAINT) (MOD-BLOCK TYPE) | 646.71 | - |
| | | | | | | 125 | 125 | EA | LINE STRIPING TARGETS | 646.76 | EST |
| | | | | | | 250 | 250 | SF | REMOVAL OF EXISTING PAVEMENT MARKINGS | 646.85 | EST |
| | | | | | | 300 | 300 | SY | GEOTEXTILE FOR ROADBED SUBGRADE SEPARATOR | 649.11 | EST |
| | | | | 280 | | | 280 | SY | GEOTEXTILE FOR SILT FENCE | 649.51 | |
| | | | | 20 | | | 20 | LB | SEED | 651.15 | EST |
| | | | | 125 | | | 125 | LB | FERTILIZER | 651.18 | EST |
| | | | | .5 | | | .5 | TON | AGRICULTURAL LIMESTONE | 651.20 | EST |
| | | | | .5 | | | .5 | TON | HAY MULCH | 651.25 | EST |
| | | | | 10 | | | 10 | SY | SODDING | 651.30 | EST |
| | | | | 110 | | | 110 | CY | TOPSOIL | 651.35 | EST |
| | | | | 1 | | | 1 | LS | EROSION PREVENTION & SEDIMENT CONTROL PLAN | 652.10 | |
| | | | | 100 | | | 100 | HR | MONITORING EROSION PREVENTION & SEDIMENT CONTROL PLAN | 652.20 | |
| | | | | 1 | | | 1 | LU | MAINTENANCE OF EROSION PREVENTION & SEDIMENT CONTROL PLAN (NABI) | 652.30 | |
| | | | | 500 | | | 500 | SY | EROSION MATTING | 654.10 | EST |
| | | | | | | 98 | 98 | SF | TRAFFIC SIGNS, TYPE A | 675.20 | .51 |
| | | | | | | | | | ***BEGIN SIGN POSTS OPTION *** | | |
| | | | | | | 265 | 265 | LF | FLANGED CHANNEL SIGN POST | 675.301 | 1.5 |
| | | | | | | 265 | 265 | LF | SQUARE TUBE SIGN POSTS AND ANCHOR | 675.341 | 1.5 |
| | | | | | | | | | ***END SIGN POSTS OPTION *** | | |
| | | | | | | 12 | 12 | EA | REMOVING SIGNS | 675.50 | |
| | | | | | | 12 | 12 | EA | ERECTING SALVAGED SIGNS | 675.60 | |
| | | | 1 | | | | 1 | EA | TRAFFIC CONTROL SIGNAL SYSTEM - INT. | 678.15 | |
| | | | | | | 50 | 50 | LF | ELECTRICAL CONDUIT (2") (PVC). | 678.21 | |
| | | | | | | 1150 | 1150 | LF | VEHICLE LOOP DETECTOR | 678.22 | |
| | | | | | | 350 | 350 | LF | WIRED CONDUIT (1 1/2") | 678.23 | |
| | | | | | | 950 | 950 | LF | WIRED CONDUIT (2") | 678.23 | |
| | | | | | | 100 | 100 | LF | ELECTRICAL WIRING | 678.24 | |
| | | | | | | 6 | 6 | EA | JUNCTION BOX | 678.26 | |
| | | | | | | 250 | 250 | LF | ELECTRICAL CONDUIT SLEEVE (8") | 678.30 | |

## DETAILED SUMMARY OF QUANTITIES

| QUANTITIES | UNIT | ITEMS |
|---|---|---|

## DETAILED SUMMARY OF QUANTITIES

| QUANTITIES | UNIT | ITEMS |
|---|---|---|

PROJECT NAME: *SWANTON*
PROJECT NUMBER: *STPG ST 036-1(11)*

FILE NAME: *PW:\TRAFFIC DES.\00b150\tb150tit.dgn*
PROJECT LEADER: *B. NYQUIST*
DESIGNED BY: *TRAFFIC DESIGN*
*tb105q02.1*

PLOT DATE: 26-APR-2006
DRAWN BY: *TRAFFIC DESIGN*
CHECKED BY: *TRAFFIC DESIGN*
SHEET 5 OF 45