

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
						ROADWAY	EROSION CONTROL	BRIDGE	FULL C & E ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
						450				450		CY	COMMON EXCAVATION	203.15				
								325		325		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
						1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22		1106.75	CY	SUB TOTAL
								550		550		CY	STRUCTURE EXCAVATION	204.25		3.25	CY	ROUNDING
								175		175		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30		1110	CY	TOTAL FILL AVAILABLE
						330				330		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10		0	CY	TOTAL FILL REQUIRED
													BEGIN OPTION AA			1110	CY	TOTAL WASTE
						400				400		CY	SUBBASE OF GRAVEL	301.15				
						400				400		CY	SUBBASE OF CRUSHED GRAVEL, COARSE GRADED	301.25				
						400				400		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35				
													END OPTION AA					
						25				25		CY	AGGREGATE SURFACE COURSE	401.10				
						1				1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
								10		10		GAL	WATER REPELLENT, SILANE	514.10				
								1		1		EACH	REMOVAL OF STRUCTURE (7'-8" x 5'-5" x 60'-0" CGMPPA)	529.15				
								1		1		LS	PRECAST CONCRETE STRUCTURE (14'-0" x 7'-0" x 60'-0" BOX)	540.10				
								250		250		CY	STONE FILL, TYPE II	613.11				
						225				225		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21				
						200				200		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED/NESTED W/8 FEET POSTS	621.217				
						500				500		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
								100		100		TON	CRUSHED STONE BEDDING	629.54				
						400				400		HR	FLAGGERS	630.15				
									1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
									1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
									2000	2000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
						1				1		LS	MOBILIZATION/DEMOLITION	635.11				
						500				500		LF	4 INCH WHITE LINE	646.20				
						500				500		LF	4 INCH YELLOW LINE	646.21				
								300		300		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11				
								400		400		SY	GEOTEXTILE UNDER STONE FILL	649.31				
							120			120		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
							120			120		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
							5			5		LB	SEED	651.15				
							5			5		LB	SEED, WINTER RYE	651.17				
							40			40		LB	FERTILIZER	651.18				
							0.1			0.1		TON	AGRICULTURAL LIMESTONE	651.20				
							0.1			0.1		TON	HAY MULCH	651.25				
							30			30		CY	TOPSOIL	651.35				
							1			1		LS	EPSC PLAN	652.10				

PROJECT NAME: BRIGHTON
PROJECT NUMBER: STP 034-3(2)

FILE NAME: s00b246excel.dgn
PROJECT LEADER: K. HIGGINS
DESIGNED BY: J. SALVATORI
QUANTITY SHEET 1

PLOT DATE: 25-JUN-2012
DRAWN BY: J. SALVATORI
CHECKED BY: W. LAMMER
SHEET 4 OF 30