

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES													TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES							
													FULL E&C ITEMS	EROSION CONTROL	ROADWAY	BRIDGE QUANTITY	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS	
															1		1			LS	CLEARING AND GRUBBING (INCLUDING INDIV. TREES & STUMPS)	201.10			BITUMINOUS CONCRETE PAVEMENT (PG 58 - 28)	
															2207		3	2210			CY	COMMON EXCAVATION	203.15	382	TON	1.5" TYPE III
															3804		6	3810			CY	SOLID ROCK EXCAVATION	203.16	479	TON	2" TYPE II
															188		12	200			CY	EARTH BORROW	203.30	605	TON	2.5" TYPE I
															5868		32	5900			SY	FINE GRADING-SUBGRADE	203.40	180	TON	TEMPORARY DETOUR
														28	52			80			CY	TRENCH EXCAVATION OF EARTH	204.20	36	TON	ROUND
															3			3			CY	TRENCH EXCAVATION OF ROCK	204.21	1700	TON	TOTAL
															1233		17	1250			SY	DRILLING AND BLASTING OF SOLID ROCK SUBGRADE	205.20			TEMPORARY EROSION CONTROL
															318		7	325			SY	COLD PLANING-BIT PAVEMENT	210.10	28	CY	TRENCH EXCAVATION OF EARTH
															533		17	550			SY	SCARIFYING PAVEMENT	212.20	130	CY	SUBBASE OF DENSE GRADED CRUSHED STONE
														130	2655		15	2800			CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	130	CY	SUBBASE OF DENSE GRADED CRUSHED STONE
															11		1	12			CWT	EMULSIFIED ASPHALT	404.65	13	CY	STONE FILL, TYPE I
															1700			1700			TON	BITUMINOUS CONCRETE PAVEMENT (PG 58-28)	406.25	120	CY	GEOTEXTILE FABRIC FOR SILT FENCE
															58			58			LF	18" PCCSP(PI) .064 (2-2/3X1/2)	601.0615	1	TON	HAY MULCH
															18		2	20			LF	36" PCCSP .079 (2-2/3 X 1/2)	601.0446	17	LB	SEED - WINTER RYE
															3			3			CY	CEMENT RUBBLE MASONRY	602.15	30	EA	HAY BALES
															68		2	70			MGAL	DUST CONTROL WITH WATER	609.10			
															1			1			TON	DUST & ICE CONTROL WITH CALCIUM CHLORIDE	609.15			
														45			5	50			CY	STONE FILL, TYPE I	613.10			
															2			2			EACH	YIELDING MARKER POSTS	619.17			
															310		15	325			LF	REMOVING OF EXISTING FENCE	620.55			
															100			100			LF	TEMPORARY TRAFFIC BARRIER	621.90			
															500			500			HR	UNIFORMED TRAFFIC OFFICERS	630.10			
															800			800			HR	FLAGGERS	630.15			
														1				1			LS	FIELD OFFICE-ENGINEERS	631.10			
														1				1			LS	TESTING EQUIPMENT - CONCRETE	631.16			
														1				1			LS	TESTING EQUIPMENT - BITUMINOUS	631.17			
														1				1			LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25			
															1			1			LS	MOBILIZATION	635.10			
															1			1			LS	TRAFFIC CONTROL	641.10			
															2900		100	3000			LF	4" WHITE LINE	646.20			
															2900		100	3000			LF	4" YELLOW LINE	646.21			
															2900		100	3000			LF	TEMPORARY 4" WHITE LINE	646.60			
															400			400			LF	TEMPORARY 4" WHITE LINE (TAPE - TYPE II)	646.60			
															4100			4100			LF	TEMPORARY 4" YELLOW LINE	646.61			
															800			800			LF	TEMPORARY 4" YELLOW LINE (TAPE - TYPE II)	646.61			
															156		4	160			EACH	LINE STRIPING TARGETS	646.73			
															1981		19	2000			SY	GEOTEXTILE FOR ROADBED SUBGRADE SEPARATOR (DETOUR)	649.11			
															1920		30	1950			SY	GEOTEXTILE FOR SILT FENCE	649.51			
														68			2	70			LB	SEED	651.15			

PROJECT NAME: **SUDBURY**
PROJECT NUMBER: **ST 0161 (10)**
FILE NAME: 0 PLOT DATE: 12/20/01
PROJECT LEADER: ABJ DRAWN BY: JAS
DESIGNED BY: 0 CHECKED BY: 0
QUANTITY SHEET #1 SHEET 4 OF 34