

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
					ROADWAY	EMPLOYEE TRAINEESHIP	EROSION CONTROL	BRIDGE	FULL C E	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					1					1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
					585					585		CY	COMMON EXCAVATION	203.15				
					250					250		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
					1					1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
								230		230		CY	STRUCTURE EXCAVATION	204.25				
								110		110		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
					300					300		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
					465					465		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35				
					1					1		CWT	EMULSIFIED ASPHALT	404.65				
					1					1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
					200					200		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30				
					1					1		LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32				
								118		118		CY	CONCRETE, HIGH PERFORMANCE CLASS B (FPQ)	501.34				
								1		1		LS	FURNISHING EQUIPMENT FOR DRIVING PILING	504.10				
								390		390		LF	STEEL PILING FOR INTEGRAL ABUTMENTS, HP 14 X 102	505.29				
								2		2		EACH	DYNAMIC PILE LOADING TEST	505.45				
								9800		9800		LB	REINFORCING STEEL (FPQ)	507.15				
								13100		13100		LB	EPOXY COATED REINFORCING STEEL (FPQ)	507.17				
								227		227		EACH	MECHANICAL BAR CONNECTOR (#5)	507.19				
								560		560		LF	PRESTRESSED CONCRETE BOX BEAMS (27" X 48") (FPQ)	510.21				
								490		490		LF	GROUTING SHEAR KEYS (FPQ)	510.24				
								30		30		GAL	WATER REPELLENT, SILANE	514.10				
								54		54		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG (FPQ)	516.10				
								1		1		LS	MAINTENANCE OF STRUCTURES AND APPROACHES	527.10				
					120					120		SY	REMOVAL OF BRIDGE PAVEMENT	529.10				
					1					1		EACH	REMOVAL OF STRUCTURE (1040 SF - EST.)	529.15				
								8		8		EACH	BEARING DEVICE ASSEMBLY, ELASTOMERIC PAD (11 1/2" X 11 1/2")	531.11				
								16		16		EACH	BEARING DEVICE ASSEMBLY, ELASTOMERIC PAD (5 3/4" X 11 1/2")	531.11				
					125					125		CY	STONE FILL, TYPE II	613.11				
					150					150		CY	STONE FILL, TYPE IV	613.13				
					89					89		LF	REMOVAL OF EXISTING FENCE	620.55				
					4					4		EACH	MANUFACTURED TERMINAL SECTION, TANGENT	621.61				
					257					257		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
					3000					3000		HR	FLAGGERS	630.15				
									1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
									1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
									1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
								3000		3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
					520					520		HR	EMPLOYEE TRAINEESHIP	634.10				
					1					1		LS	MOBILIZATION/DEMOBILIZATION	635.11				

PROJECT NAME: EAST HAVEN
PROJECT NUMBER: BRF 0269(II)

FILE NAME: s00cl62qs.xls
PROJECT LEADER: K. HIGGINS
DESIGNED BY: J. LACROIX
QUANTITY SHEET - 1

PLOT DATE: 08-AUG-2011
DRAWN BY: R. PELLETT
CHECKED BY: J. LACROIX
SHEET 4 OF 40