

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							PARK-AND-RIDE	LANDSCAPING	EROSION CONTROL	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10	-			203.16 SOLID ROCK EXCAVATION
							1280				1280		CY	COMMON EXCAVATION	203.15	14			ESTIMATED QUANTITY - ASSUME MATERIAL NOT AVAILABLE FOR FILL
							15				15		CY	SOLID ROCK EXCAVATION	203.16	EST.			SEE SHEET 6 FOR EARTHWORKS SUMMARY
							1680				1680		CY	EARTH BORROW	203.30	13			
							1560				1560		CY	SAND BORROW	203.31	13			
							1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-			
							1440				1440		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	7			
							2				2		CY	AGGREGATE SURFACE COURSE	401.10	0.5			
							6				6		CWT	EMULSIFIED ASPHALT	404.65	1			
							500				500		TON	BITUMINOUS CONCRETE PAVEMENT	406.25	2			
							1				1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-			
							120				120		LB	REINFORCING STEEL	507.15	1			
							2				2		CY	CONCRETE, CLASS B	541.25	0.5			
							10				10		HR	POWER BROOM RENTAL, TYPE I	608.30	EST.			
							260				260		MGAL	DUST CONTROL WITH WATER	609.10	10			
							10				10		CY	STONE FILL, TYPE I	613.10	3			
							305				305		LF	VERTICAL GRANITE CURB	616.21	4			
							85				85		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	3			
							10				10		SF	DETECTABLE WARNING SURFACE	618.30	-			
							50				50		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
							300				300		HR	FLAGGERS	630.15	EST.			
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16	-			
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
							1				1		LS	MOBILIZATION/DEMobilIZATION	635.11	-			
							1				1		LS	TRAFFIC CONTROL	641.10	-			
							1975				1975		LF	DURABLE 4 INCH WHITE LINE	646.400	20			
							100				100		LF	DURABLE 4 INCH YELLOW LINE	646.410	4			
							21				21		LF	DURABLE 24 INCH STOP BAR	646.480	-			
							8				8		EACH	DURABLE LETTER OR SYMBOL	646.490	-			
							3740				3740		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11	10			
							300				300		SY	GEOTEXTILE UNDER STONE FILL	649.31	2			
							110				110		SY	GEOTEXTILE FOR UNDERDRAIN TRENCH LINING	649.41	2			
									265		265		SY	GEOTEXTILE FOR SILT FENCE	649.51	12			
								100			100		LB	SEED	651.15	3			
								250			250		LB	FERTILIZER	651.18	6			
								1			1		TON	AGRICULTURAL LIMESTONE	651.20	-			
								1.5			1.5		TON	HAY MULCH	651.25	0.3			
								265			265		CY	TOPSOIL	651.35	5			

PROJECT NAME: ENOSBURG  
PROJECT NUMBER: CMG PARK(20)

FILE NAME: ...04-05QuantitySheet.pxf PLOT DATE: 5/23/2011  
PROJECT LEADER: WLD DRAWN BY: STANTEC  
DESIGNED BY: CSP/GGG CHECKED BY: GAS  
QUANTITY SHEET 1 SHEET 4 OF 32

