

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
			ALTERNATE A	ALTERNATE B	ALTERNATE C	PARK-AND-RIDE	LANDSCAPING	EROSION CONTROL	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10	-			ITEM 204.25 - STRUCTURAL EXCAVATION
						0.5				0.5		ACRE	THINNING AND TRIMMING	201.30	0.32	3	CY	DRAINAGE
						10				10		CY	STRUCTURE EXCAVATION	204.25	-	5	CY	BUS SHELTER FOOTING
						10				10		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30	-	8	CY	SUBTOTAL
						1900				1900		LB	REINFORCING STEEL	507.15	-	2	CY	ROUNDING
						1				1		GAL	WATER REPELLENT, SILANE	514.10	0.6	10	CY	TOTAL
						60				60		LF	METAL HAND RAILING	525.15	4			ITEM 204.30 - GRANULAR BACKFILL FOR STRUCTURES
						30				30		CY	CONCRETE, CLASS B	541.25	-	3	CY	DRAINAGE
						2				2		EACH	12" CPEPES	601.7005	-	5	CY	BUS SHELTER FOOTING
						4				4		EACH	18" CPEPES	601.7015	-	8	CY	SUBTOTAL
						1				1		EACH	CONCRETE MANHOLE WITH CAST IRON COVER	604.11	-	2	CY	ROUNDING
						4				4		EACH	CAST IRON GRATE WITH FRAME, TYPE A	604.45	-	10	CY	TOTAL
						10				10		HR	POWER GRADER RENTAL	608.15	EST.			ITEM 507.15 - REINFORCING STEEL
						10				10		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.	312	LBS	CONCRETE STAIRS
						10				10		HR	POWER BROOM RENTAL, TYPE I	608.30	EST.	134	LBS	BUS SHELTER FOOTING
						10				10		HR	TRUCK RENTAL	608.37	EST.	621	LBS	ISLANDS
						10				10		HR	LOADER RENTAL, TYPE I	608.40	EST.	824	LBS	DRAINAGE
						220				220		MGAL	DUST CONTROL WITH WATER	609.10	8	1891	LBS	SUBTOTAL
						5				5		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	4	9	LBS	ROUNDING
						390				390		CY	STONE FILL, TYPE I	613.10	4	1900	LBS	TOTAL
						340				340		CY	STONE FILL, TYPE II	613.11	8			ITEM 541.25 - CONCRETE, CLASS B
						830				830		LF	VERTICAL GRANITE CURB	616.21	-	15	CY	STAIRS
						330				330		LF	REMOVING AND RESETTNG CURB	616.40	5	1.5	CY	FOOTING FOR BUS SHELTER
						56				56		LF	REMOVAL OF EXISTING CURB	616.41	-	9.8	CY	DRAINAGE
						15				15		TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	1	3.7	CY	ROUNDING
						280				280		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	6	30	CY	TOTAL
						80				80		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 8 INCH	618.11	9			ITEM 613.11 - STONE FILL, TYPE II
						5				-5-0		EA	WOOD MARKER POSTS	619.15	-	82	CY	DRAINAGE
						100				100		HR	UNIFORMED TRAFFIC OFFICERS	630.10	5	250	CY	ESTIMATED 1:2 CUT SLOPE STABILIZATION
						400				400		HR	FLAGGERS	630.15	EST.	332	CY	SUBTOTAL
									1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-	8	CY	ROUNDING
									1	1		LS	TESTNG EQUIPMENT, CONCRETE	631.16	-	340	CY	TOTAL
									1	1		LS	TESTNG EQUIPMENT, BITUMINOUS	631.17	-			ITEM 616.21 - VERTICAL GRANITE CURB
									1	1		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	-	176	LF	BUS LOOP
						1				1		LS	TRAFFIC CONTROL	641.10	-	106	LF	ACCESS ROAD
						3350				3350		LF	DURABLE 4 INCH WHITE LINE	646.400	6	394	LF	ISLANDS
						1750				1750		LF	DURABLE 4 INCH YELLOW LINE	646.410	7	148	LF	PARKING LOT
						55				55		LF	DURABLE 24 INCH STOP BAR	646.480	3	824	LF	SUBTOTAL
						33				33		EACH	DURABLE LETTER OR SYMBOL	646.490	-	6	LF	ROUNDING
						430				430		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	1	830	LF	TOTAL



PROJECT NAME: RANDOLPH
PROJECT NUMBER: CMG PARK(2)IS

FILE NAME: ...03_zk000quantities_manual.ppt DATE: 8/3/2007
PROJECT LEADER: WLD DRAWN BY: STANTEC
DESIGNED BY: STANTEC CHECKED BY: GAS
QUANTITY SHEET 1 SHEET 6 OF 63