STATE OF VERMONT
AGENCY OF TRANSPORTATION

ITEM DETAIL SHEET

CURB

BEGIN STATION	END STATION	POSITION LEFT FT	POSITION RIGHT FT	REMARKS
ITEM 616.21 - VERTICAL GRANITE CURB				
ISLAND 1				
0+85	1+10	65		
BUS LOOP				
10+11	11+81		176	
ACCESS ROAD				
1+32	1+81	106		
PARKING LOT				
21+52	23+27	148		
PARKING LOT ISLAND				
21+75	23+05		329	
Subtotals		319	505	
Round		1	5	
Totals		320	510	
ITEM 616.40 - REMOVING AND RESETTING CURB				
51+42	53+02	325		
Subtotals		325		
Round		5		
Totals		330		
ITEM 616.41 - REMOVAL OF EXISTING CURB				
51+33	51+41	28		
53+14	53+15	28		
Subtotals		56		
Round		-		
Totals		56		

SIDEWALK

BEGIN STATION	END STATION	POSITION LEFT SY	POSITION RIGHT SY	REMARKS
ITEM 618.10 - PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH				
BUS LOOP				
10+11	11+81		121	
ACCESS ROAD				
1+32	1+81	53		
PARKING LOT				
21+75	23+27	82		
BICYCLE RACK				
11+09	11+22		18	
Subtotals		135	139	
Round		5	1	
Totals		140	140	
ITEM 618.11 - PORTLAND CEMENT CONCRETE SIDEWALK, 8 INCH				
LEFT TURN LANE ISLAND				
51+42	52+77	71		
Subtotals		71		
Round		9		
Totals		80		
ITEM 900.675 - SPECIAL PROVISION (STAMPED CONCRETE ISLAND, 8 INCH)				
ISLAND 1				
0+85	1+10	22		
ISLAND 2				
10+83	11+38		30	
Subtotals		22	30	
Round		4	4	
Totals		26	34	

GUARD RAIL

BEGIN STATION	END STATION	POSITION LEFT FT	POSITION RIGHT FT	END TREATMENT BEGIN EA	END TREATMENT END EA

UNDERDRAIN

BEGIN STATION	END STATION	TYPE	POSITION	DIA. IN	LENGTH FT	TRENCH EARTH CY	TRENCH ROCK CY	GRAN BKFILL CY	FB EA	MKR PST EA
~~ALTERNATE 'A'~~										
~~ITEM 605.10 - 6 INCH UNDERDRAIN~~										
~~21+25~~	~~23+27~~	~~U1~~	~~RT~~	~~6~~	~~201~~	~~119~~			~~1~~	
~~0+72~~	~~3+40~~	~~U2~~	~~RT~~	~~6~~	~~268~~	~~159~~			~~1~~	
~~21+51~~	~~23+27~~	~~U4~~	~~RT~~	~~6~~	~~173~~	~~68~~			~~1~~	
~~21+82~~	~~23+27~~	~~U5~~	~~LT~~	~~6~~	~~141~~	~~84~~			~~1~~	
~~1+36~~	~~1+84~~	~~U6~~	~~LT~~	~~6~~	~~66~~	~~39~~				
~~10+09~~	~~10+83~~	~~U7~~	~~RT~~	~~6~~	~~90~~	~~48~~				
~~10+93~~	~~12+29~~	~~U8~~	~~RT~~	~~6~~	~~187~~	~~39~~			~~1~~	
~~11+51~~	~~12+46~~	~~U9~~	~~LT~~	~~6~~	~~82~~	~~24~~			~~1~~	~~1~~
SUBTOTAL					1209	581			6	1
ROUNDING					91	-			-	-
TOTAL					1300	581			6	1
ALTERNATE 'B' AND 'C'										
ITEM 605.10 - 6 INCH UNDERDRAIN										
23+24	1+02	U1	RT.	6	459	284			1	
23+33	23+40	U2	RT,LT	6	169	104			1	
1+82	1+36	U11	LT.	6	56	32			1	
10+09	10+83	U12	RT.	6	90	47				
10+93	12+29	U13	RT.	6	187	39			1	
11+51	12+46	U14	LT.	6	82	24			1	1
SUBTOTAL					1043	530			5	1
ROUNDING					17	1			-	-
TOTAL					1060	531			5	1
ALTERNATE 'B' AND 'C'										
ITEM 900.640 - SPECIAL PROVISION (6 INCH UNDERDRAIN PIPE, POROUS PAVEMENT)										
23+30	22+39	U3	RT.	6	100	54			1	
21+48	22+35	U4	RT.	6	91	49			1	
22+95	22+06	U6	RT.	6	129	64			1	
21+21	22+02	U7	RT.	6	90	51			1	
22+87	21+83	U9	LT.	6	104	63			1	
21+22	21+80	U10	LT.	6	58	34			1	
SUBTOTAL					572	315			6	1
ROUNDING					18	-			-	-
TOTAL					590	315			6	1
ALTERNATE 'B' AND 'C'										
ITEM 900.640 - SPECIAL PROVISION (12 INCH UNDERDRAIN PIPE, POROUS PAVEMENT)										
22+05	22+36	U5	RT.	12	70	58				
22+00	21+81	U8	RT,LT	12	43	35				
SUBTOTAL					113	93				
ROUNDING					7	1				
TOTAL					120	94				

Stantec

PROJECT NAME: RANDOLPH
PROJECT NUMBER: CMG PARK(21)S

FILE NAME: ...\04_zk000Item Detail.ptf
PROJECT LEADER: WLD
DESIGNED BY: STANTEC
ITEM DETAIL SHEET

PLOT DATE: 8/3/2007
DRAWN BY: STANTEC
CHECKED BY: GAS
SHEET 10 OF 63