

QUANTITY SHEET



SUMMARY OF ESTIMATED QUANTITIES									
	PARK & RIDE	LAND-SCAPING	EROSION CONTROL	FULL E&C	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
	3				3	EA	REMOVING MEDIUM TREES	201.15	-
	700				700	CM	COMMON EXCAVATION	203.15	6.6
	170				170	CM	EXCAVATION OF SURFACES AND PAVEMENTS	203.28	5
	820				820	CM	EARTH BORROW	203.30	10
	70				70	CM	SAND BORROW	203.31	10
	470				470	CM	TRENCH EXCAVATION OF EARTH	204.20	16
	1040				1040	CM	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	4.5
	420				420	KG	EMULSIFIED ASPHALT	404.65	9
	680				680	T	BITUMINOUS CONCRETE PAVEMENT (PG 58-28)	406.25	3.9
	3				3	CM	CONCRETE, CLASS B	501.25	0.8
	110				110	KG	REINFORCING STEEL	507.15	7.6
	4				4	L	WATER REPELLENT (MOD. - SILANE)	514.10	1.3
	120				120	M	450MM CPEP	601.0915	5.5
	5				5	EA	PRECAST REINFORCED CONC. CATCH BASIN WITH CAST IRON GRATE	604.20	-
	60				60	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST
	8				8	HR	POWER BROOM RENTAL, TYPE II	608.31	EST
	1.5				1.5	T	DUST AND ICE CONTROL W/CALCIUM CHLORIDE	609.15	-
			15		15	CM	STONE FILL, TYPE I	613.10	2.2
			10		10	CM	STONE FILL, TYPE I (MOD. - INLET PROTECTION)	613.10	-
			40		40	CM	STONE FILL, TYPE I (MOD. - CONSTRUCTION ENTRANCE)	613.10	-
	60				60	M	VERTICAL GRANITE CURB	616.21	3.2
	115				115	SM	PORTLAND CEMENT CONCRETE SIDEWALK, 125 mm (1200 WIDTH)	618.10	3.2
	50				50	SM	PORTLAND CEMENT CONCRETE SIDEWALK, 125 mm (1500 WIDTH)	618.10	8
	37.5				37.5	M	STEEL BEAM GUARD RAIL (GALVANIZED)	621.20	-
	2				2	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	-
	37.5				37.5	M	REMOVAL AND DISPOSAL OF GUARD RAIL	621.80	-
	40				40	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
	250				250	HR	FLAGGERS	630.15	EST
				1	1	LS	FIELD OFFICE - ENGINEERS	631.10	-
				1	1	LS	TESTING EQUIPMENT - CONCRETE	631.16	-
				1	1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	-
				1	1	LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25	-
	1				1	LS	MOBILIZATION / DEMOBILIZATION	635.11	-
	1				1	LS	TRAFFIC CONTROL (MOD.)	641.10	-
	810				810	M	DURABLE 100MM WHITE LINE (EPOXY PAINT)	646.40	15
	14				14	M	DURABLE 100MM YELLOW LINE (EPOXY PAINT)	646.41	1.4

SUMMARY OF ESTIMATED QUANTITIES									
	PARK & RIDE	LAND-SCAPING	EROSION CONTROL	FULL E&C	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
	8				8	M	DURABLE 600MM STOP BAR (EPOXY PAINT)	646.46	1.5
	14				14	EA	DURABLE LETTER OR SYMBOL (EPOXY PAINT)	646.50	-
	50				50	SM	GEOTEXTILE FOR ROADBED SUBGRADE SEPARATOR	649.11	7.4
			30		30	SM	GEOTEXTILE UNDER STONE FILL	649.31	8.7
			210		210	SM	GEOTEXTILE FOR SILT FENCE	649.51	6.3
	25				25	KG	SEED	651.15	5.2
	170				170	KG	FERTILIZER	651.18	12
	1.5				1.5	T	AGRICULTURAL LIMESTONE	651.20	0.2
	1.5				1.5	T	HAY MULCH	651.25	0.2
	250	15			15	CM	CEDAR BARK MULCH	651.27	4.7
					250	CM	TOPSOIL	651.35	13
			1		1	LS	EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.10	-
			40		40	HR	MONITORING EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.20	EST
			1		1	LU	MAINTENANCE OF EROSION PREVENTION & SEDIMENT CONTROL PLAN (N.A.B.I.)	652.30	-
				450	450	SM	EROSION MATTING	654.10	13
				12	12	EA	EVERGREEN SHRUBS (PFITZERANIA COMPACTA - COMPACT JUNIPER) (7.6L CONTAINER)	656.25	-
				14	14	EA	DECIDUOUS TREES (ACER SACCHARUM - SUGAR MAPLE) (50-64mm CAL, B&B)	656.30	-
				24	24	EA	DECIDUOUS SHRUBS (HEMEROCALLIS "STELLA DE ORO" - DAYLILLIES) (3.8L CONTAINER)	656.35	-
	1				1	LS	ROADSIDE REST FACILITY (BUILDING)	658.10	-
	1				1	LS	ROADSIDE REST FACILITY (BUILDING) (MOD. - SALVAGE)	658.10	-
	1				1	EA	REST AREA BENCH (MOD. - BIKE RACK)	658.20	-
	1.64				1.64	SM	TRAFFIC SIGNS, TYPE A	675.20	-
	23				23	M	FLANGED CHANNEL SIGN POST	675.301	-
	13				13	EA	REMOVING SIGNS	675.50	-
	3				3	EA	ERECTING SALVAGED SIGNS	675.60	-
	320				320	M	ELECTRICAL CONDUIT (50mm)	678.21	4.5
	370				370	M	ELECTRICAL WIRING	678.24	18
	40				40	M	ELECTRICAL CONDUIT SLEEVE (2 X 150mm DIA.)	678.30	3.3
	10				10	EA	LIGHT POLE BASE	679.21	-
	4				4	EA	REMOVE & RESET LIGHT POLE (MOD.)	679.25	-
	1				1	EA	POWER STANCHION	679.28	-
	6				6	EA	LIGHT POLE	679.45	-
	7				7	EA	BRACKET ARM	679.47	-
	7				7	EA	LUMINAIRE	679.50	-

PROJECT NAME: ST. ALBANS PARK & RIDE
 PROJECT NUMBER: CMG PARK (23)S
 FILE NAME: 10/14/2005 2:46:50 PM
 PROJECT LEADER: JWT
 DRAWN BY: PGJ
 DESIGNED BY: PGJ
 CHECKED BY: EPD
 QUANTITY SHEET
 SHEET 4 OF 29