STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET #2

| MILEMARKER, STATION, OR SIGN NUMBER | SIGN LEGEND | REMOVAL | SIGN DIMENSIONS EA | WIDTH (In) | HEIGHT (In) | NEW & SALVAGED SIGNS "A" | "B" | SALV SIGN | SALV TIS | EXIST POST RETAIN | SALVAGE | NEW SIGN POSTS NO. OF POSTS | SQUARE STEEL (In) 1.75 lb/ft 1.88 | 2.0 lb/ft 2.42 | 2.5 lb/ft 3.35 | ANCHOR | SLEEVE | TUBULAR ALUMINUM Ø (In) 3.0 lb/ft 1.3 | 4.0 lb/ft 1.7 | 4.0 MOD lb/ft 1.7 | FOUND-ATION | TUBULAR STEEL Ø (In) 3.0 lb/ft 7.6 | 3.5 lb/ft 9.0 | 4.0 lb/ft 10.8 | 5.0 lb/ft 14.6 | W-SHAPE STEEL FTG. SIZE 24" | 30" | WEIGHT | POST SIZE | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL DETAIL ON SHEET NUMBER | STD. SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NEWFANE MM 2.928 LT TH 1 | STOP | 1 | 1 | 30 | 30 | 6.25 | | | | | | 1 | | 13.0 X | | X | | | | | | | | | | | | | | | | RI-1 | | |
| NEWFANE MM 2.932 LT TH 1 | LEGAL LOAD LIMIT 24,000 POUNDS | 1 | 1 | 24 | 30 | 5.00 | | | | | | 1 | | 16.0 X | | X | | | | | | | | | | | | | | | | VR-017 | | E-141 |
| NEWFANE MM 2.932 LT TH 1 | SPEED LIMIT 25 | 1 | | | | | | 1 | | | | | | | | | | | | | | | | | | | | | | | | SALVAGE EXISTING SIGN MOUNT BELOW LEGAL LOAD LIMIT SIGN | | |
| NEWFANE MM 2.932 RT TH 56 | LEGAL LOAD LIMIT 24,000 POUNDS | 1 | 1 | 24 | 30 | 5.00 | | | | | | 1 | | 13.5 X | | X | | | | | | | | | | | | | | | | VR-017 | | E-141 |
| NEWFANE MM 2.938 RT TH 56 | STOP | 1 | 1 | 30 | 30 | 6.25 | | | | | | 1 | | 13.5 X | | X | | | | | | | | | | | | | | | | RI-1 | | |
| NEWFANE MM 2.955 RT TH 16 | LEGAL LOAD LIMIT 24,000 POUNDS | 1 | 1 | 24 | 30 | 5.00 | | | | | | 1 | | 13.5 X | | X | | | | | | | | | | | | | | | | VR-017 | | E-141 |
| NEWFANE MM 2.960 RT TH 16 | STOP | 1 | 1 | 30 | 30 | 6.25 | | | | | | 1 | | X | | X | | | | | | | | | | | | | | | | RI-1 EXISTING POST USED (DRILLED INTO PAVEMENT) | | |
| NEWFANE MM 2.975 LT TH 1 | STOP | 1 | 1 | 30 | 30 | 6.25 | | | | | | 1 | | 13.75 X | | X | | | | | | | | | | | | | | | | RI-1 | | |
| NEWFANE MM 2.980 LT TH 1 | LEGAL LOAD LIMIT 24,000 POUNDS | 1 | 1 | 24 | 30 | 5.00 | | | | | | 1 | | 13.25 X | | X | | | | | | | | | | | | | | | | VR-017 | | E-141 |
| NEWFANE MM 3.094 LT TH 14 | LEGAL LOAD LIMIT 24,000 POUNDS | 1 | 1 | 24 | 30 | 5.00 | | | | | | 1 | | 15.25 X | | X | | | | | | | | | | | | | | | | VR-017 | | E-141 |
| | SPEED LIMIT 25 | 1 | | | | | | 1 | | | | | | | | | | | | | | | | | | | | | | | | SALVAGE EXISTING SIGN MOUNT BELOW LEGAL LOAD LIMIT SIGN | | |
| NEWFANE MM 3.095 LT TH 14 | ONE WAY | 1 | 1 | 36 | 12 | 3.00 | | | | | | 1 | | 12.0 X | | X | | | | | | | | | | | | | | | | R6-1L BACK TO BACK | | |
| | ONE WAY | 1 | 1 | 36 | 12 | 3.00 | | | | | | | | | | | | | | | | | | | | | | | | | | R6-1R | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | 13 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND VTRANS "SIGN POST DESIGN GUIDELINE." | | | | | | | | | | | | | FT | FT 150 | FT | | EA | LB | LB | LB | | LB | LB | LB | LB | | | | | | | | |
| | | | SHEET TOTALS | SF 56.00 | SF | EA. 2 | EA. | | | | | | FT 150 123.75 | | | | | LB | | | EA. | LB | | | | EA. | EA. | LB | | | | | |

TRAFFIC SIGN SUMMARY SHEET #2

PROJECT NAME: NEWFANE-TOWNSHEND
PROJECT NUMBER: STP 2401(1)

FILE NAME: p01b036.dgn
PROJECT LEADER: CRB
DESIGNED BY: JBZ
IPARM FILE NAME: p01b036_24.I

PLOT DATE: 04-FEB-2010
DRAWN BY: JBZ
CHECKED BY: BDB
SHEET 24 OF 32