

ITEM NO.	ITEM DESCRIPTION	UNIT	CHANNEL	SUPER-STRUCTURE	APPROACH SLAB 1	ABUTMENT 1	PIER	ABUTMENT 2	APPROACH SLAB 2	BRIDGE SUBTOTAL	ROADWAY	EROSION CONTROL	FULL E & C	TOTAL	FINAL	REMARKS
580.13	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE, CLASS I	SY				5		5		10				10		ESTIMATED QUANTITY
580.14	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE, CLASS II	SY				5		5		10				10		ESTIMATED QUANTITY
580.15	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE, CLASS III	CY				1		1		2				2		ESTIMATED QUANTITY
608.25	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	HR										2		2		
613.10	STONE FILL, TYPE I	CY										10		10		
613.10	STONE FILL, TYPE I (MOD. I-CHECK DAMS)	CY										5		5		
613.10	STONE FILL, TYPE I (MOD. II-TRACKING PAD)	CY										20		20		
613.11	STONE FILL, TYPE II	CY				40		20		60				60		
617.10	RELOCATE MAILBOX, SINGLE SUPPORT	EA									1			1		
620.70	SNOW FENCE (MOD. - PDF)	LF										1190		1190		
621.21	HEAVY DUTY STEEL BEAM GUARD RAIL (GALVANIZED)	LF									214			214		
621.60	ANCHOR FOR STEEL BEAM RAIL	EA									4			4		
621.80	REMOVAL AND DISPOSAL OF GUARD RAIL	LF									185			185		
621.90	TEMPORARY TRAFFIC BARRIER	LF									130			130		
630.15	FLAGGERS	HR									100			100		
631.10	FIELD OFFICE - ENGINEERS	LS											1	1		
631.16	TESTING EQUIPMENT - CONCRETE	LS											1	1		
631.17	TESTING EQUIPMENT - BITUMINOUS	LS											1	1		
631.18	TESTING EQUIPMENT - PROTECTIVE COATINGS	LS											1	1		
631.25	FIELD OFFICE - TELEPHONE (N.A.B.I.)	LU											1	1		
635.11	MOBILIZATION / DEMOBILIZATION	LS								1				1		
641.10	TRAFFIC CONTROL	LS									1			1		
646.20	4 INCH WHITE LINE	LF									1160			1160		
646.41	DURABLE 4 INCH YELLOW LINE (THERMOPLASTIC)	LF									1040			1040		
646.60	TEMPORARY 4 INCH WHITE LINE	LF									1370			1370		
646.61	TEMPORARY 4 INCH YELLOW LINE	LF									200			200		
646.66	TEMPORARY 24 INCH STOP BAR	LF									50			50		
646.76	LINE STRIPING TARGETS	EA									26			26		

N. A. B. I. = NOT A BID ITEM

**TOWN OF GRAFTON  
CAMBRIDGEPORT BRIDGE**

Town Of	GRAFTON	Bridge No.	16G
Highway No.	TH 1	Log Sta.	
		Surv. Sta.	
TH 1 (CAMBRIDGEPORT BRIDGE) OVER THE SAXTONS RIVER			
<b>QUANTITY SHEET (2 OF 3)</b>			
Designed By	J. T. KLEIN	Drawn By	B. J. MASSE
Checked By	Date	Bridge Design Supervisor	
J. A. MERCER	6/05	M. A. COLGAN	Date 6/05
PROJECT	GRAFTON	PROJECT NO.	TH2-0104

I.G.C. Info.  
File No. 51335QNT2  
Sheet 4 of 42

**VHB Vanasse Hangen Brustlin, Inc.**

VHB NO. 51335

plot date: 6/13/2005