STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (IN)	HEIGHT (IN)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL LB/FT 1.12	2.0	3.0	SQUARE STEEL (IN) LB/FT 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (IN) LB/FT 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (IN) FOUND-ATION	LB/FT 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
VT ROUTE 35/121																																			
13+75 LT	SOUTH 35 ↑	1	24	12	2.0																														E-136C
		1	24	24	4.0						1			16 X			X																		E-136C
		1	21	15	2.2																														E-136C
13+75 LT	EAST 121 ←	1	24	12	2.0																														E-136C
		1	30	24	5.0						1			16 X			X																		E-136C
		1	21	15	2.2																														E-136C
14+50 RT	NORTH 35 / WEST 121	1	24	12	2.0																														E-136C
		1	24	12	2.0																														E-136C
		1	24	24	4.0						1			14 X			X																		E-136C
		1	30	24	5.0																														E-136C
15+75 LT*	← CAMBRIDGEPORT	1	72	12	6.0																														E-123
	← SAXTONS RIVER 3	1	72	12	6.0						2 +			14 X			X																		E-123
	TOWNSHEND 10 ↑	1	72	12	6.0									14																					E-123
16+75 RT*	GRAFTON 4	1	72	12	6.0						2 +			12 X			X																		E-123
	CHESTER 11	1	72	12	6.0									12																					E-123
PARKER HILL RD																																			
40+25 LT	STOP	1	30	30	6.3						1			14 X			X																R1-1		E-143
					SF 66.7							FT	FT	FT 12 ~~90~~	FT	FT	FT 90		EA	LB	LB	LB		LB	LB	LB	LB							
	TOTALS				SF 66.7	SF —	EA. —	SF —				FT 90			FT 90					LB —			EA. —	LB —				EA. —	EA. —	LB —				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

FLANGED CHANNEL OR SQUARE STEEL LENGTH = 15 FT

* STATIONING INTERPOLATED FROM PROPOSED PROJECT ALIGNMENTS

VHB Vanasse Hangen Brustlin, Inc.

TOWN OF GRAFTON
CAMBRIDGEPORT BRIDGE

Town Of GRAFTON	Bridge No. 16G
Highway No. TH 1	Log Sta. / Surv. Sta.
TH 1 (CAMBRIDGEPORT BRIDGE) OVER THE SAXTONS RIVER	
TRAFFIC SIGN SUMMARY SHEET (2 OF 3)	
Designed By J. A. MERCER	Drawn By B. J. MASSE
Checked By J. T. KLEIN Date 5/05	Bridge Design Supervisor M. A. COLGAN Date 5/05
PROJECT GRAFTON	PROJECT NO. TH2-0104
I.G.C. Info.	
File No. 51335TS3	Sheet 11 of 42

VHB NO. 51335

plot date: 5/27/2005