STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (IN)	HEIGHT (IN)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL LB/FT 1.12	2.0	3.0	SQUARE STEEL (IN) LB/FT 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (IN) LB/FT 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (IN) FOUNDATION	LB/FT 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
VT ROUTE 121																																				
20+50 LT	SOUTH 35 ←	1	24	12	2.0						1			16 X			X																		E-136C	
		1	24	24	4.0																														E-136C	
		1	21	15	2.2																														E-136C	
20+50 LT	NORTH 35 → / WEST 121 →	1	24	12	2.0						2 ~~1~~			16 X 16			X																		E-136C	
		1	24	12	2.0																														E-136C	
		1	24	24	4.0																														E-136C	
		1	30	24	5.0																														E-136C	
		1	21	15	2.2																														E-136C	
		1	21	15	2.2																														E-136C	
21+60 LT	TH1 CAMBRIDGEPORT RD	1	72	12	6.0						2 ~~1~~			12 X 12			X																•CAMBRIDGEPORT RD DID NOT PUT UP LEFT WITH TOWN OF GRAFTON WRONG NAME		E-123	
	TH42 PARKER HILL RD	1	72	12	6.0																														E-123	
22+00 RT	EAST 121	1	24	12	2.0						1			14 X			X																		E-136C	
		1	30	24	5.0																														E-136C	
13+50 ~~22+50~~ LT	← ATHENS 1	1	72	12	6.0						2 ~~1~~			14 X 14			X																		E-123	
	← TOWNSHEND 10	1	72	12	6.0																														E-123	
	GRAFTON 4 →	1	72	12	6.0																														E-123	
23+50 RT	CAMBRIDGEPORT	1	72	12	6.0						2 ~~1~~			12 X 12			X																		E-123	
	SAXTONS RIVER 3	1	72	12	6.0																														E-123	
24+50 LT	JCT 35	1	21	15	2.2						1			14 X			X																			
		1	24	24	4.0																														E-136C	
23+40 RT	BRIDGE FREEZE (SALVAGE SIGN)													14																						
					SF 80.8							FT	FT	FT 166 ~~105~~	FT	FT	FT 105		EA	LB	LB	LB		LB	LB	LB	LB								
	TOTALS				SF 80.8	SF —	EA. —	SF —				FT 105			FT 105					LB —			EA. —	LB —				EA. —	EA. —	LB —					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

FLANGED CHANNEL OR SQUARE STEEL LENGTH = 15 FT

VHB Vanasse Hangen Brustlin, Inc.

TOWN OF GRAFTON
CAMBRIDGEPORT BRIDGE

Town Of GRAFTON	Bridge No. 16G
Highway No. TH 1	Log Sta. / Surv. Sta.
TH 1 (CAMBRIDGEPORT BRIDGE) OVER THE SAXTONS RIVER	
TRAFFIC SIGN SUMMARY SHEET (3 OF 3)	
Designed By J. A. MERCER	Drawn By B. J. MASSE
Checked By J. T. KLEIN Date 5/05	Bridge Design Supervisor M. A. COLGAN Date 5/05
PROJECT GRAFTON	PROJECT NO. TH2-0104
I.G.C. Info.	
File No. 51335TS4	Sheet 12 of 42

VHB NO. 51335 plot date: 5/27/2005