STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"A" MOD.	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) kg/m 44 3.4	SQUARE STEEL (mm) kg/m 50 3.9	SQUARE STEEL (mm) kg/m 63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	TUBULAR ALUMINUM Ø (mm) kg/m 100 2.5	TUBULAR ALUMINUM Ø (mm) kg/m 100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	TUBULAR STEEL Ø (mm) kg/m 89 13.4	TUBULAR STEEL Ø (mm) kg/m 100 16.1	TUBULAR STEEL Ø (mm) kg/m 125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
SALISBURY: 3+217.8, RT	0070 0117 0200	1	900	900	0.81						2			X		X																			59	E-138M
		1	150	200	0.03																															
3+277.8, RT		1	1800	500	0.90						2			X		X																			59	E-123M
3+330.0, LT	0070 0117 0207	1	750	750	0.56						1			X		X																		BACK-TO-BACK		E-143M
		1	150	200	0.03																															E-138M
3+330.0, LT	HOLMAN RD						1				1		X			X																		SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON FLANGED CHANNEL SIGN POST.	-	-
3+344.0, LT		1	600	750	0.45						1			X		X																				E-141M
3+397.8, LT		1	1800	500	0.90						2			X		X																			59	E-123M
3+602.0, LT		1	900	900	0.81						2			X		X																			59	
3+815.0, LT		1	600	750	0.45						1			X		X																				E-142M
3+862.4, LT	0070 0117 0240	1	150	200	0.03						1	X			X																					E-138M
												m 4.6	m 4.6	m 59.7	m 4.6	m 64.3	m		EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS		m^2 4.97	m^2	EA 1	m^2							m 68.9			m 68.9					kg			EA	kg				EA	EA	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: SALISBURY - MIDDLEBURY	PROJECT NO.: NH 2311(1)S
DESIGN FILE NAME: pave/01b018/pb018.dgn	
IPARM FILE NAME: pb018t02.i	PLOT DATE: 0-JUL-2006 13:3
SURVEYED BY: N/A	SURVEY DATE: N/A
SQUAD LEADER: D.E.G.	DRAWN BY: C.A.K.
	SHEET: 36 OF 67