STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 7

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"A" MOD.	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
SALISBURY: 6+115.5, LT	0070 0117 0380	1	150	200	0.03						1	X			X																				E-138M
6+437.4, RT	0070 0117 0400	1	150	200	0.03						1	X			X																				E-138M
6+571.0, RT	BRIDGE 124A US 7	1	150	200	0.03						1	X			X																				E-134M
6+574.0, LT	BRIDGE 124A US 7	1	150	200	0.03						1	X			X																				E-134M
6+759.3, LT	0070 0117 0420	1	150	200	0.03						1	X			X																				E-138M
7+081.1, RT	0070 0117 0440	1	150	200	0.03						1	X			X																				E-138M
7+285.5, LT	SALISBURY | MIDDLEBURY	1	1500	190	0.29						2			X		X																				E-124M
	0070 0117 0453	1	150	200	0.03																															E-138M
	0070 0111 0000	1	150	200	0.03																															E-138M
											m	m	m	m	m	m	EA	kg	kg	kg		kg	kg	kg	kg									
											27.6		9.2	27.6	9.2																				
TOTALS		m^2 0.53	m^2	EA	m^2						m 36.8			m 36.8				kg	EA	kg						EA	EA	kg						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: SALISBURY - MIDDLEBURY
PROJECT NO.: NH 2311(1)S

DESIGN FILE NAME: pave/01b018/pb018.dgn
IPARM FILE NAME: pb018t07.1
SURVEYED BY: N/A
SQUAD LEADER: D.E.G.
PLOT DATE: 10-JUL-2006 13:3
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 41 OF 67