STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 8

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"A" MOD.	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
MIDDLEBURY:																																			
0+018.0, RT	BRIDGE 124B US 7	1	150	200	0.03						1	X			X																				E-134M
0+020.0, LT	BRIDGE 124B US 7	1	150	200	0.03						1	X			X																				E-134M
0+321.9, RT	0070 0117 0020	1	150	200	0.03						1	X			X																				E-138M
0+643.7, LT	0070 0117 0040	1	150	200	0.03						1	X			X																				E-138M
0+965.6, RT	0070 0117 0060	1	150	200	0.03						1	X			X																				E-138M
1+010.0, LT		1	300	900	0.27						1			X		X																			E-107M
1+010.0, RT		1	300	900	0.27						1			X		X																			E-107M
	BRIDGE 125 US 7	1	150	200	0.03																														E-134M
1+090.0, LT		1	300	900	0.27						1			X		X																			E-107M
	BRIDGE 125 US 7	1	150	200	0.03																														E-134M
TOTALS		m^2 1.02	m^2	EA	m^2							m 23.0	m	m 13.8	m 23.0	m 13.8	m		EA	kg	kg	kg		kg	kg	kg	kg								
												m 36.8			m 36.8					kg			EA	kg				EA	EA	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: SALISBURY - MIDDLEBURY
PROJECT NO.: NH 2311(1)S

DESIGN FILE NAME: pave/01b018/pb018.dgn
IPARM FILE NAME: pb018t08.i
SURVEYED BY: N/A
SQUAD LEADER: D.E.G.
PLOT DATE: 10-JUL-2006 13:3
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 42 OF 67