STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 13

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"A" MOD.	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 / 3.4	50 / 3.9	63 / 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 / 1.9	100 / 2.5	100 MOD / 2.5	TUBULAR STEEL Ø (mm) FOUND-ATION	75 / 11.3	89 / 13.4	100 / 16.1	125 / 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
MIDDLEBURY: I+952.0, RT	NORTH / EAST	1	600	300	0.18						2												2	66.1								X			E-136AM
		1	600	300	0.18																														E-136BM
	7 / VERMONT 125	1	600	600	0.36																														E-136AM
		1	750	600	0.45																														E-136BM
	↑ / →	1	525	375	0.20																														E-136AM
		1	525	375	0.20																														E-136BM
	TO / TO	1	600	300	0.18																														E-136BM
		1	600	300	0.18																														E-136BM
	WEST / NORTH	1	600	300	0.18																														E-136BM
		1	600	300	0.18																														E-136BM
	VERMONT 125 / VERMONT 116	1	750	600	0.45																														E-136BM
		1	750	600	0.45																														E-136BM
	↑ / →	1	525	375	0.20																														E-136BM
		1	525	375	0.20																														E-136BM
I+962.0, C/L		1	600	600	0.36						1			X		X			X														SLEEVE REQUIRED FOR SIGN POST; INCIDENTAL TO SIGN POST ITEM BACK - TO - BACK		E-143M
		1	600	750	0.45																														E-144M
		1	450	450	0.20																												BACK - TO - BACK		E-150M
		1	450	450	0.20																														E-150M
I+969.0, LT		1	1200	600	0.72						2			X		X																			E-152M
I+987.0, RT	STOP / 0070 0111 0123	1	750	750	0.56						1			X		X			X														SLEEVE REQUIRED FOR SIGN POST; INCIDENTAL TO SIGN POST ITEM BACK - TO - BACK		E-143M
		1	150	200	0.03																														E-138M
I+992.0, C/L		1	600	750	0.45						1			X		X			X														SLEEVE REQUIRED FOR SIGN POST; INCIDENTAL TO SIGN POST ITEM BACK - TO - BACK		E-144M
		1	600	600	0.36																														E-143M
		1	450	450	0.20																												BACK - TO - BACK		E-150M
		1	450	450	0.20																														E-150M
												m 23.0			m 23.0				EA	kg				kg 66.1										
TOTALS			m² 7.32		m²	EA	m²					m 23.0			m 23.0				EA	kg			EA 2	kg 66.1				EA	EA	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: SALISBURY - MIDDLEBURY	PROJECT NO.: NH 2311(1)S
DESIGN FILE NAME: pave/01b018/pb018.dgn	
IPARM FILE NAME: pb018t13.1	PLOT DATE: 10-JUL-2006 13:3
SURVEYED BY: N/A	SURVEY DATE: N/A
SQUAD LEADER: D.E.G.	DRAWN BY: C.A.K.
	SHEET: 47 OF 67