STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 16

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"A" MOD.	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
MIDDLEBURY:																																			
2+277.0, RT	SPEED LIMIT 50	1	600	750	0.45						1			X		X																			E-142M
2+367.0, LT	JCT	1	525	375	0.20						1			X		X																			E-136BM
	VERMONT 125	1	750	600	0.45																														E-136BM
2+427.0, LT		1	900	900	0.81						2			X		X																			E-151M
2+570.0, LT	0070 0111 0160	1	150	200	0.03						1	X			X																			E-138M
2+628.0, RT	BRIDGE 126A US 7	1	150	200	0.03						1	X			X																			E-134M
2+631.0, LT	BRIDGE 126A US 7	1	150	200	0.03						1	X			X																			E-134M
											m 13.8	m	m 18.4	m 13.8	m 18.4	m		EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS		m^2 2.00	m^2	EA	m^2						m 32.2			m 32.2					kg			EA	kg				EA	EA	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: SALISBURY - MIDDLEBURY
PROJECT NO.: NH 2311(1)S

DESIGN FILE NAME: pave/01b018/pb018.dgn
IPARM FILE NAME: pb018t16.i
SURVEYED BY: N/A
SQUAD LEADER: D.E.G.

PLOT DATE: 10-JUL-2006 13:30
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 50 OF 67