STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 18

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (mm)	SIGN DIMENSIONS HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "A" MOD.	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) kg/m 44 3.4	SQUARE STEEL (mm) kg/m 50 3.9	SQUARE STEEL (mm) kg/m 63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	TUBULAR ALUMINUM Ø (mm) kg/m 100 2.5	TUBULAR ALUMINUM Ø (mm) kg/m 100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	TUBULAR STEEL Ø (mm) kg/m 89 13.4	TUBULAR STEEL Ø (mm) kg/m 100 16.1	TUBULAR STEEL Ø (mm) kg/m 125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
MIDDLEBURY:																																			
3+540.6, LT	0070 0117 0220	1	150	200	0.03						1	X			X																			E-138M
3+862.4, LT	0070 0117 0240	1	150	200	0.03						1	X			X																			E-138M
4+082.0, LT	MIDDLE ROAD SOUTH						1				1		X			X																	SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON FLANGED CHANNEL SIGN POST.	-	-
4+082.0, LT	STOP 0070 0111 0255	1 1	750 150	750 200	0.56 0.03						1			X		X																	BACK-TO-BACK		E-143M E-138M
4+098.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS						1				1			X		X																	SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-
4+098.0, LT	STOP						1				1			X		X																	SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-
4+110.0, RT	STOP						1				1			X		X																	SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-
4+110.0, RT	LEGAL LOAD LIMIT 24,000 POUNDS						1				1			X		X																	SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-
4+123.0, RT	STOP 0070 0111 0256	1	150	200	0.03		1				1			X		X																	SALVAGED SIGN TO BE MOUNTED ON NEW POST. BACK-TO-BACK		E-138M
												m 9.2	m 4.6	m 27.6	m 9.2	m 32.2	m		EA	kg	kg	kg		kg	kg	kg	kg							
TOTALS			m² 0.68	m²	EA 6	m²						m 41.4			m 41.4					kg			EA	kg				EA	EA	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: SALISBURY - MIDDLEBURY	PROJECT NO.: NH 2311(1)S
DESIGN FILE NAME: pave/01b018/pb018.dgn	
IPARM FILE NAME: pb018t18.I_	PLOT DATE: 10-JUL-2006 13:3
SURVEYED BY: N/A	SURVEY DATE: N/A
SQUAD LEADER: D.E.G.	DRAWN BY: C.A.K.
	SHEET: 52 OF 67