STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

				TRAINING	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
						1960	1960	CM	EARTH BORROW	203.30	
						1	1	CM	TRENCH EXCAVATION OF EARTH (NOT A BID ITEM)	204.20	
						36000	36000	SM	COLD PLANING-BITUMINOUS PAVEMENT	210.10	
						1143	1143	T	AGGREGATE SHOULDERS	402.12	
						5185	5185	T	AGGREGATE SHOULDERS (MOD.)	402.12	
						322242	322242	KG	EMULSIFIED ASPHALT	404.65	
						1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (NOT A BID ITEM)	406.50	
						40750	40750	T	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 58-34)	490.30	
					1		1	CM	CONCRETE, CLASS A	501.22	EST.
					100		100	KG	REINFORCING STEEL	507.15	EST.
					40		40	M	BRIDGE EXPANSION JOINT (ASPHALTIC PLUG TYPE)	516.10	
					10		10	L	JOINT SEALER, POLYURETHANE	524.20	EST.
					45		45	M	REMOVAL OF EXISTING RAILING	525.10	
					21		21	M	BRIDGE RAILING-HD STEEL BEAM/FASCIA MOUNTED (MOD. 1)	525.41	
					21		21	M	BRIDGE RAILING-HD STEEL BEAM/FASCIA MOUNTED (MOD. 2)	525.41	
					1		1	EA	PARTIAL REMOVAL OF STRUCTURE	529.20	
						3	3	EA	CHANGING ELEV. OF DROP INLETS, CATCH BASINS OR MANHOLES	604.40	
						10	10	EA	REHABING DI, CB, OR MH CLASS I	604.412	
						260	260	HR	POWER GRADER RENTAL	608.15	
						260	260	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	
						172	172	HR	POWER BROOM RENTAL	608.30	
						260	260	HR	POWER BROOM RENTAL, TYPE II	608.31	
						260	260	HR	TRUCK RENTAL	608.37	
						260	260	HR	LOADER RENTAL, TYPE I	608.40	
						1250	1250	CM	STONE FILL, TYPE I	613.10	
						660	660	M	TREATED TIMBER CURB	616.35	
						7025	7025	M	STEEL BEAM GUARD RAIL	621.20	
						250	250	M	STEEL BEAM GUARD RAIL W/2.4 METER POSTS (MOD.)	621.20	
						55	55	M	HEAVY DUTY STEEL BEAM GUARD RAIL	621.21	
						98	98	EA	MANUFACTURED TERMINAL SECTION (FLARED)	621.505	
						4	4	EA	GUARD RAIL APPROACH SECTION, TYPE I	621.70	
						2	2	EA	GUARD RAIL APPROACH SECTION, TYPE II	621.71	
						7880	7880	M	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	
						2070	2070	HR	UNIFORMED TRAFFIC OFFICERS	630.10	
						4650	4650	HR	FLAGGERS	630.15	

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 58-34)
24991	T	TYPE IIIS
15553	T	TYPE IVS
206	T	ROUNDING
40750	T	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: LUDLOW-MT. HOLLY
PROJECT NUMBER: STP 2327(1)S

FILE NAME: /pave/01b024/pb024.dgn
PROJECT LEADER: WOOLAVER
DESIGNED BY: LOCKE
pb024qsl.1
PLOT DATE: 21-FEB-2006 13:5
DRAWN BY: LOCKE
CHECKED BY: WOOLAVER
SHEET 4 OF 84