STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
LUDLOW:																																			
5+793.0, LT	1030 1410 0360	1	150	200	0.03						1	X	X 3.00		X																				E-138M
5+868.0, LT	LOCUST HILL TH54						2				1		X 3.00			X																		SALVAGED SIGNS TO BE MOUNTED ON NEW POST BACK TO BACK. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON POST.	-	-
5+868.0, LT	STOP 1030 1410 0365	1 1	750 150	750 200	0.56 0.03						1			X 4.3		X																		BACK-TO-BACK		E-143M E-138M
5+880.0, RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X 4.20		X																				E-141M
5+882.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X 4.3		X																				E-141M
5+899.0, RT	STOP 1030 1410 0366	1 1	750 150	750 200	0.56 0.03						1			X 3.8		X																		BACK-TO-BACK		E-143M E-138M
5+900.0, RT	FOX LANE TH17						2				1		X 3.5			X																		SALVAGED SIGNS TO BE MOUNTED ON NEW POST BACK TO BACK. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON POST.	-	-
											m 4.6	m 9.2	m 13.8	m 4.6	m 23.0	m		EA	kg	kg	kg		kg	kg	kg	kg								
											26.1																									
TOTALS			m^2 2.11	m^2	EA 4	m^2					m 27.6			m 27.6					kg	EA	kg						EA	EA	kg					

ARCHIVED ON CADD

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT:	PROJECT NO.:
LUDLOW- MT. HOLLY	NH 2327(I)S

DESIGN FILE NAME: /pave/01b024/pb024.dgn
IPARM FILE NAME: pb024tss2.i
SURVEYED BY: N/A
SQUAD LEADER: D.E.G.
PLOT DATE: $DATE$
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 45 OF 84