STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 13

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) kg/m 44 3.4	SQUARE STEEL (mm) kg/m 50 3.9	SQUARE STEEL (mm) kg/m 63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	TUBULAR ALUMINUM Ø (mm) kg/m 100 2.5	TUBULAR ALUMINUM Ø (mm) kg/m 100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	TUBULAR STEEL Ø (mm) kg/m 89 13.4	TUBULAR STEEL Ø (mm) kg/m 100 16.1	TUBULAR STEEL Ø (mm) kg/m 125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
MT. HOLLY: I+650.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X 4.3		X																			E-141M
I+685.0, RT		1	300	900	0.27						1			X 3.0		X																			E-107M
	BRIDGE 33 VT 103	1	150	200	0.03																														E-134M
I+685.0, LT		1	300	900	0.27						1			X 3.0		X																			E-107M
I+726.0, RT		1	300	900	0.27						1			X 3.0		X																			E-107M
I+726.0, LT		1	300	900	0.27						1			X 3.0		X																			E-107M
	BRIDGE 33 VT 103	1	150	200	0.03																														E-134M
I+829.5, LT	GREENSTAND RD TH43						1				1		X 3.0			X																		SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON FLANGED CHANNEL POST.	-	-
I+830.0, LT	STOP 1030 1112 0114	1 1	750 150	750 200	0.56 0.03						1			X 4.3		X																		BACK-TO-BACK		E-143M E-138M
I+841.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X 4.3		X																			E-141M
I+931.2, LT	1030 1112 0120	1	150	200	0.03						1	~~X~~	X 3.0		X																					E-138M
TOTALS					m² 2.66	m²	EA 1	m²				m 4.6	m 4.6	m 32.2	m 4.6	m 36.8	m	EA	kg	kg	kg	EA	kg	kg	kg	kg	EA	EA	kg						
												m 30.90			m 41.4																			
															m 41.4				kg			EA	kg				EA	EA	kg						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

ARCHIVED ON CADD

PROJECT: LUDLOW- MT. HOLLY

PROJECT NO.: NH 2327(I)S

DESIGN FILE NAME: /pave/01b024/pb024.dgn
IPARM FILE NAME: pb024tssl3.i
SURVEYED BY: N/A
SQUAD LEADER: D.E.G.

PLOT DATE: $DATE$
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 56 OF 84