STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 14

Not Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
MT. HOLLY: 2+253.1, RT	1030 1112 0140	1	150	200	0.03						1	~~X~~	X 3.0		X																				E-138M
2+440.0, LT	SPEED LIMIT 50	1	600	750	0.45						1		~~X~~	X 4.3		X																				E-142M
2+500.0, LT	SOUTH	1	600	300	0.18						1		~~X~~	X 4.3		X																				E-136BM
	VERMONT 103	1	750	600	0.45																															E-136BM
2+521.0, LT	GREENSTAND RD TH43						1				1		X 3.7			X																		SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON FLANGED CHANNEL POST.	-	-
2+521.0, LT	STOP 1030 1112 0157	1 1	750 150	750 200	0.56 0.03						1			X 4.3		X																		BACK-TO-BACK		E-143M E-138M
2+530.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X 4.3		X																				E-141M
2+566.0, RT	BRIDGE 34 VT 103	1	150	200	0.03						1	~~X~~	X 3.0		X																				E-134M
2+576.0, LT	STOP 1030 1112 0161	1 1	750 150	750 200	0.56 0.03						1			X 4.3		X																		BACK-TO-BACK		E-143M E-138M
	BRIDGE 34 VT 103	1	150	200	0.03																															E-134M
2+593.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X 4.3		X																				E-141M
2+610.0, RT	STOP 1030 1112 0163	1 1	750 150	750 200	0.56 0.03						1			X 4.3		X																		BACK-TO-BACK		E-143M E-138M
2+611.0, RT	SAWYER HILL ROAD						1				1		X 3.7			X																		SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON FLANGED CHANNEL POST.	-	-
2+612.0, RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X 4.3		X																				E-141M
TOTALS					m² 4.29	m²	EA 2	m²				m 9.2	m 9.2	m 36.8	m 9.2	m 46.0	m		EA	kg	kg	kg		kg	kg	kg	kg	EA	EA	kg					
														47.80																					
															m 55.2																					
																m 55.2																				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

ARCHIVED ON CADD

PROJECT:	PROJECT NO.:
LUDLOW- MT. HOLLY	NH 2327(I)S
DESIGN FILE NAME: /pave/01b024/pb024.dgn	
IPARM FILE NAME: pb024tssl4.i	PLOT DATE: $DATE$
SURVEYED BY: N/A	SURVEY DATE: N/A
SQUAD LEADER: D.E.G.	DRAWN BY: C.A.K.
	SHEET: 57 OF 84