STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 19

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
MT. HOLLY: 5+770.0, RT	BRIDGE 36 VT_103	1	150	200	0.03						1	~~X~~	X 3.0		X																				E-134M
5+773.0, LT	BRIDGE 36 VT_103	1	150	200	0.03						1	~~X~~	X 3.0		X																				E-134M
5+793.6, RT	1030 1112 0360	1	150	200	0.03						1	~~X~~	X 3.0		X																				E-138M
6+115.5, LT	1030 1112 0380	1	150	200	0.03						1	~~X~~	X 3.0		X																				E-138M
6+260.0, RT	BRIDGE 36A VT_103	1	150	200	0.03						1	~~X~~	X 3.0		X																				E-134M
6+265.0, LT	BRIDGE 36A VT_103	1	150	200	0.03						1	~~X~~	X 3.0		X																				E-134M
6+340.0, RT	PARKING AREA AHEAD	1	600	750	0.45						1			X 4.3		X																	75	
6+437.4, RT	1030 1112 0400	1	150	200	0.03						1	~~X~~	X 3.0		X																				E-138M
6+518.0, RT	PARKING AREA	1	600	750	0.45						1			X 4.3		X																	75	
6+650.0, RT		1	750	750	0.56						1			X 4.9		X																	75	
6+700.0, LT	PARKING AREA	1	600	750	0.45						1			X 4.3		X																	75	
6+787.5, LT	SUMMIT RD TR42						1				1		X 3.0			X																	SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON FLANGED CHANNEL POST.	-	-
6+788.0, LT	STOP 1030 1112 0423	1 1	750 150	750 200	0.56 0.03						1			X 4.3		X																	BACK-TO-BACK		E-143M E-138M
6+880.0, LT	PARKING AREA AHEAD	1	600	750	0.45						1			X 4.3		X																	75	
											m 32.2	m 4.6	m 27.6	m 32.2	m 32.2	m		EA	kg	kg	kg		kg	kg	kg	kg								
												50.40																							
TOTALS					~~3.13~~ 3.16	m²	EA 1	m²				m 64.4			m 64.4					kg			EA	kg				EA	EA	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

ARCHIVED ON CADD

PROJECT:	PROJECT NO.:
LUDLOW- MT. HOLLY	NH 2327(I)S
DESIGN FILE NAME: /pave/01b024/pb024.dgn	
IPARM FILE NAME: pb024tssl9.i	PLOT DATE: $DATE$
SURVEYED BY: N/A	SURVEY DATE: N/A
SQUAD LEADER: D.E.G.	DRAWN BY: C.A.K.
	SHEET: 62 OF 84