STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 22

MAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) kg/m 44 3.4	SQUARE STEEL (mm) kg/m 50 3.9	SQUARE STEEL (mm) kg/m 63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	TUBULAR ALUMINUM Ø (mm) kg/m 100 2.5	TUBULAR ALUMINUM Ø (mm) kg/m 100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUND-ATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	TUBULAR STEEL Ø (mm) kg/m 89 13.4	TUBULAR STEEL Ø (mm) kg/m 100 16.1	TUBULAR STEEL Ø (mm) kg/m 125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
MT. HOLLY: 8+445.0, LT	SOUTH	1	600	300	0.18						1			X 4.9		X																		E-136BM
	VERMONT 103	1	750	600	0.45																														E-136BM
8+454.0, RT	BRIDGE 39 VT 103	1	150	200	0.03						1	~~X~~	X 3.0		X																				E-134M
8+457.0, LT	BRIDGE 39 VT 103	1	150	200	0.03						1	~~X~~	X 3.7		X																				E-134M
8+473.0, LT	R X R	1			0.64						1			X 4.9		X																		E-190M
8+473.0, RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X 4.3		X																		E-141M
8+476.5, LT	BELMONT RD						1				1		X 3.7			X																	SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON FLANGED CHANNEL POST.	-	-
8+477.0, LT	STOP; 1030 1112 0528	1 1	750 150	750 200	0.56 0.03						1			X 4.3		X																	BACK-TO-BACK		E-143M E-138M
8+495.0, ~~LT~~ RT	STOP; 1030 1112 0528	1 1	750 150	750 200	0.56 0.03						1			X 4.3		X																	BACK-TO-BACK		E-143M E-138M
											m	m 9.2	m 4.6	m 23.0	m 9.2	m 27.6	m		EA	kg	kg	kg		kg	kg	kg	kg							
													33.10																						
TOTALS			m^2 2.96	m^2	EA 1	m^2					m 36.8				m 36.8					kg			EA	kg				EA	EA	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

ARCHIVED ON CADD

PROJECT: LUDLOW- MT. HOLLY	PROJECT NO.: NH 2327(I)S
DESIGN FILE NAME: /pave/0lb024/pb024.dgn	
IPARM FILE NAME: pb024tss22.I	PLOT DATE: $DATE$
SURVEYED BY: N/A	SURVEY DATE: N/A
SQUAD LEADER: D.E.G.	DRAWN BY: C.A.K.
	SHEET: 65 OF 84