STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 30

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
MT. HOLLY:																																			
12+200.0, LT	SOUTH / WEST	1	600	300	0.18						2			X 12.20		X																X		E-136BM
		1	600	300	0.18																														E-136BM
	VERMONT 103 / VERMONT 140	1	750	600	0.45																														E-136BM
		1	750	600	0.45																														E-136BM
	↑ / →	1	525	375	0.20																														E-136BM
		1	525	375	0.20																														E-136BM
12+222.0, RT	NORTH	1	600	300	0.18						1			X 4.3		X																		E-136BM
	VERMONT 103	1	750	600	0.45																														E-136BM
	1030 1112 0760	1	150	200	0.03																														E-142M
12+260.0 LT	↑ MOUNT HOLLY 2	1	1800	250	0.45						2			X 11.00		X																			E-123M
	↑ LUDLOW 11	1	1800	250	0.45																														E-123M
12+295.0 RT	E. CLAREDNDON 6	1	1800	250	0.45						2			X 8.5		X																			E-123M
	RUTLAND 14	1	1800	250	0.45																														E-123M
	BRIDGE 44 VT_103	1	150	200	0.03																														E-134M
12+310.0, LT	JCT	1	600	300	0.18						1			X 4.9		X																			E-136BM
	VERMONT 140	1	750	600	0.45																														E-136BM
	BRIDGE 44 VT_103	1	150	200	0.03																														E-134M
12+404.824 LT	MOUNT HOLLY / WALLINGFORD	1	1500	190	0.29						1			X 4.3		X																			E-124M
	1030 1125 0000	1	150	200	0.03																														E-138M
												m	m	m 41.4	m	m 41.4	m		EA	kg	kg	kg		kg	kg	kg	kg								
												45.20																								
TOTALS			m² 5.13	m²	EA	m²						m 41.4			m 41.4					kg	EA	kg		EA	EA	kg									

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

ARCHIVED ON CADD

PROJECT:	PROJECT NO.:
LUDLOW- MT. HOLLY	NH 2327(1)S

DESIGN FILE NAME: /pave/01b024/pb024.dgn
IPARM FILE NAME: pb024tss30.i
SURVEYED BY: N/A
SQUAD LEADER: D.E.G.
PLOT DATE: $DATE$
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 73 OF 84