

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES					TOTALS	DESCRIPTIONS			
	ROADWAY	BRIDGE	EROSION CONTROL	FULL C.E.	GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUND
				1	1	LS	FIELD OFFICE, ENGINEERS	631.10	-
				1	1	LS	TESTING EQUIPMENT, CONCRETE	631.16	-
				1	1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
				3000	3000	DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-
	1				1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
	1				1	LS	TRAFFIC CONTROL	641.10	-
	2				2	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
	60200				60200	LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	409
	57000				57000	LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	414
	120				120	LF	DURABLE 6 INCH WHITE LINE, THERMOPLASTIC	646.422	5
	110				110	LF	DURABLE 6 INCH YELLOW LINE, THERMOPLASTIC	646.432	4
	270				270	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	4
	56				56	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-
	50				50	LF	DURABLE CROSSWALK MARKING, THERMOPLASTIC	646.502	1
	120000				120000	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	418
	113500				113500	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	328
	235				235	LF	TEMPORARY 6 INCH WHITE LINE, PAINT	646.622	5
	215				215	LF	TEMPORARY 6 INCH YELLOW LINE, PAINT	646.632	3
	540				540	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	8
	96				96	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-
	100				100	LF	TEMPORARY CROSSWALK MARKING, PAINT	646.702	2
	2960				2960	EA	LINE STRIPING TARGETS	646.76	25
			2780		2780	SY	GEOTEXTILE UNDER STONE FILL	649.31	23
			80		80	LB	SEED	651.15	EST.
			500		500	LB	FERTILIZER	651.18	EST.
			2		2	TON	AGRICULTURAL LIMESTONE	651.20	EST.
			2		2	TON	HAY MULCH	651.25	EST.
			50		50	CY	TOPSOIL	651.35	EST.
			2670		2670	SY	TEMPORARY EROSION MATTING	653.20	30
	40				40	SF	TRAFFIC SIGNS, TYPE A	675.20	0.4
	465				465	LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	-
	33				33	EA	REMOVING SIGNS	675.50	-
	14				14	EA	ERECTING SALVAGED SIGNS	675.60	-
	40				40	EA	DELINEATOR WITH STEEL POST	676.10	-
	28				28	EA	REMOVAL OF EXISTING DELINEATOR	676.12	-
	1				1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
	2030				2030	SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	18

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS
		GEOTEXTILE UNDER STONE FILL
2704	SY	DITCH CLEANING
53	SY	SLOPE REPAIR
23	SY	ROUNDING
2780	SY	TOTAL
		TEMPORARY EROSION MATTING
1715	SY	DITCH CLEANING
725	SY	M.T.S. CONSTRUCTION
200	SY	SEED PROTECTION
30	SY	ROUNDING
2670	SY	TOTAL

PROJECT NAME: GLOVER - BARTON
PROJECT NUMBER: STP 2318(I)

FILE NAME: p01b034.dgn
PROJECT LEADER: JLL
DESIGNED BY: MCF
IPARM FILE: p01b034qs02.i

PLOT DATE: 28-NOV-2012 15:0
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 6 OF 60