ITEM DETAIL SUMMARY SHEET 4

THIS SHEET NOT USED FOR RECORD PLANS, SEE LAYOUT SHEETS

LOCATION			MISCELLANEOUS																REMARKS
BEGIN MILE STA.	END MILE STA.	POS.	653.20 TEMP. EROSION MATTING SY	676.10 DEL.W/ STEEL POST EACH	676.12 REMOVAL OF EXIST. DEL. EACH														
BARTON																			
76+62.0	86+12.0	LT	50	2	2														INSTALL M.T.S., FLARED @ STA. 76+62.0 TO 76+99.5 AND 85+74.5 TO 86+12.0.
78+58	79+77	RT																	CONSTRUCT BITUMINOUS CONCRETE GUTTER
79+77	81+36	RT																	CONSTRUCT BITUMINOUS CONCRETE GUTTER
81+97	83+88	RT																	CONSTRUCT BITUMINOUS CONCRETE GUTTER
83+88	85+94.5	RT																	CONSTRUCT BITUMINOUS CONCRETE GUTTER
86+25	87+19	RT																	CONSTRUCT BITUMINOUS CONCRETE GUTTER
87+39	90+45	RT																	CONSTRUCT BITUMINOUS CONCRETE GUTTER
91+67.5	93+12.0	LT	25	1	1														INSTALL M.T.S., FLARED @ STA. 91+67.5 TO 92+05.0. CONNECT TO EXISTING GUARDRAIL @ STA. 93+12.0, LT
SHEET 2 SUBTOTALS:			650	37	25														* THESE TOTALS ARE CARRIED FORWARD TO THE DETAILED SUMMARY OF QUANTITIES ON THE QUANTITY SHEETS
SHEET 4 SUBTOTALS:			75	3	3														
SUBTOTALS:			725	40	28														
ROUNDING:			-	-	-														
TOTALS:			725*	40	28														

ITEM DETAIL SUMMARY SHEET #4

PROJECT NAME: GLOVER - BARTON
PROJECT NUMBER: STP 2318(1)

FILE NAME: p01b034.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p01b034idss04.i

PLOT DATE: 28-NOV-2012 15:0
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 10 OF 60