STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 02

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.42	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
GLOVER (CONT.)															OPTION ITEMS																				
200+64, LT	0160 1008 0380	1	6	10	0.42						1				X			X																	E-138
206+32, RT	BRIDGE 15 VT 16	1	6	8	0.33						1				X			X															VD-701		E-134
206+92, LT	BRIDGE 15 VT 16	1	6	8	0.33						1				X			X															VD-701		E-134
209+72, RT	0160 1008 0397	1	6	10	0.42				1																								MOUNT NEW SIGN BACK-TO-BACK AND BELOW EXISTING STOP SIGN		E-138
221+76, RT	0160 1008 0420	1	6	10	0.42						1				X			X																	E-138
229+15, LT	0160 1008 0434	1	6	10	0.42				1																								MOUNT NEW SIGN BACK-TO-BACK AND BELOW EXISTING STOP SIGN		E-138
232+85, RT	0160 1008 0440	1	6	10	0.42				1																								MOUNT NEW SIGN BACK-TO-BACK AND BELOW EXISTING VT ROUTE 122 SIGN		E-138
238+32, LT		2	18	18	2.25 2.25		~~1~~ ~~1~~				~~2~~					X		X															~~MOUNT SALVAGED SIGNS ON NEW POSTS~~	-	-
												FT	FT	FT	FT 32	FT 30	FT		EA	LB	LB	LB		LB	LB	LB	LB								
												FT			FT 62					LB			EA.	LB				EA.	EA.	LB					
TOTALS					SF ~~2.76~~ 7.26	SF	EA. ~~2~~ 0	SF																											

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

Stantec

PROJECT NAME: GLOVER - BARTON
PROJECT NUMBER: STP 2318(1)

FILE NAME: p01b034.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p01b034tss02.i

PLOT DATE: 28-NOV-2012 15:0
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 45 OF 60