STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 03

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75	SQUARE STEEL (in) lb/ft 2.0	SQUARE STEEL (in) lb/ft 2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0	TUBULAR STEEL Ø (in) lb/ft 3.5	TUBULAR STEEL Ø (in) lb/ft 4.0	TUBULAR STEEL Ø (in) lb/ft 5.0	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
															1.88	2.42	3.35			1.3	1.7	1.7		7.6	9.0	10.8	14.6								
GLOVER (CONT.)																																			
															OPTION ITEMS																				
238+47, RT	STOP 0160 1008 0451 B-B	1 1	30 6	30 10	5.00 0.42						1					X		X															RI-1 MOUNT NEW SIGN BACK-TO-BACK AND BELOW STOP SIGN		SEE FHWA SHS E-138
238+70, RT	BRIDGE 16 VT 16	1	6	8	0.33						1				X			X															VD-701		E-134
238+99, LT	BRIDGE 16 VT 16	1	6	8	0.33						1				X			X															VD-701		E-134
239+45, RT	Glover 1 Barton 4 NORTH VERMONT 16						+ + + +				2					X		X															~~MOUNT SALVAGED SIGNS ON NEW POSTS~~	-	-
242+88, LT	0160 1008 0460	1	6	10	0.42						1				X			X																	E-138
253+44, RT	0160 1008 0480	1	6	10	0.42						1				X			X																	E-138
264+00, LT	0160 1008 0500	1	6	10	0.42						1				X			X																	E-138
												FT	FT	FT	FT 40	FT 45	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 7.34	SF	EA. ~~4~~	SF				FT			FT 85					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

Stantec

PROJECT NAME: GLOVER - BARTON
PROJECT NUMBER: STP 2318(1)

FILE NAME: p01b034.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p01b034tss03.i

PLOT DATE: 28-NOV-2012 15:0
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 46 OF 60