

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
						ROADWAY	ROADWAY (NO FED. PART.)	TRAINING	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						10					10		CY	EXCAVATION OF SURFACES AND PAVEMENTS	203.28	1.6			COLD PLANING, BITUMINOUS PAVEMENT
						2450					2450		CY	EARTH BORROW	203.30	32	56505	SY	CHESTER
						1					1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST.	45283	SY	CAVENDISH
						106500					106500		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	1288	0	SY	LUDLOW
						400					400		TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	60	3424	SY	TOWN HIGHWAYS
						46000					46000		SY	RECLAIMED STABILIZED BASE	310.20	500	105212	SY	SUBTOTAL
						12050					12050		T	AGGREGATE SHOULDERS, RAP	402.13	118	1288	SY	ROUNDING
						920					920		CWT	EMULSIFIED ASPHALT	404.65	11	106500	SY	TOTAL
						1					1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-			AGGREGATE SHOULDERS, RAP
						45000					45000		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 64-28)	490.30	637	9427	TON	CHESTER
						1					1		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-	1701	TON	CAVENDISH
						1					1		LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-	632	TON	LUDLOW
						1					1		LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	-	34	TON	T.H. 17
						1					1		LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	-	138	TON	GUARDRAIL TERMINALS
									1		1		CY	CONCRETE, HIGH PERFORMANCE CLASS AA	501.32	0.3	11932	TON	SUBTOTAL
									845		845		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	9	118	TON	ROUNDING
									25		25		LF	REMOVAL OF EXISTING RAILING	525.10	3	12050	TON	TOTAL
									1		1		CY	REMOVAL OF CONCRETE OR MASONRY	529.25	0.3			SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 64-28)
									100		100		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	-	31267	TON	VT 103, TYPE III S, WEARING COURSE
						50					50		LF	12" CSP .064 (2-2/3 X 1/2)	601.0005	-	7584	TON	VT 103, TYPE IIS, BASE COURSE
						2					2		EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	EST.	5083	TON	VT 103, TYPE IV S, LEVELING COURSE
						1					1		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	EST.	24	TON	T.H. 17 TYPE IIS BINDER COURSE
						50					50		HR	ROADWAY PATROL MAINTENANCE	607.10	EST.	343	TON	TOWN HIGHWAYS
						250					250		HR	POWER GRADER RENTAL	608.15	EST.	62	TON	DRIVES
						245					245		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	3	44363	TON	SUBTOTAL
						255					255		HR	POWER BROOM RENTAL, TYPE I	608.30	2	637	TON	ROUNDING
						245					245		HR	TRUCK RENTAL	608.37	3	45000	TON	TOTAL
						245					245		HR	LOADER RENTAL, TYPE I	608.40	3			STONE FILL, TYPE I
						1500					1500		MGAL	DUST CONTROL WITH WATER	609.10	28	22	CY	SLOPE STABILIZATION
						600					600		CY	STONE FILL, TYPE I	613.10	47	531	CY	DITCH LOCATIONS
						20					20		TON	BITUMINOUS CONCRETE CURB, TYPE B	616.31	3.4	553	CY	SUBTOTAL
						1					1		TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	EST.	47	CY	ROUNDING
						80					80		EACH	YIELDING MARKER POSTS	619.17	EST.	600	CY	TOTAL
						26000					26000		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	339			
						2250					2250		LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205	37.5			
						135					135		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21	5			
						68					68		EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50	-			
						2					2		EACH	MANUFACTURED TERMINAL SECTION, TANGENT	621.51	-			
						23					23		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
						8					8		EACH	GUARDRAIL APPROACH SECTION, GALVANIZED TYPE I	621.70	-			

PROJECT NAME:	Chester-Ludlow	
PROJECT NUMBER:	NY 2326(1)S	
FILE NAME:	01b038	PLOT DATE:
PROJECT MANAGER:	M. Woolaver	DRAWN BY:
DESIGNED BY:	JLR	CHECKED BY:
QUANTITY SHEET #1		SHEET 8 OF 110