LOCATION			GUARDRAIL												DROP INLETS		DRAINAGE				MISCELLANEOUS					REMARKS
STATION	STATION	POS.	616.31 BIT. CURB TYPE B		621.20 STEEL BEAM GUARDRAIL GALVANIZED	621.205 STEEL BEAM GUARDRAIL GALVANIZED 8' POSTS	621.21 H.D. STEEL BEAM GUARDRAIL GALVANIZED	621.50 M.T.S. FLARED	621.51 M.T.S. TANGENT	621.60 ANCHOR FOR G.R.	621.70 APPR. SECTION GALVANIZED TYPE I	621.71 APPR. SECTION GALVANIZED TYPE II	621.80 REMOVE & DISP. G.R.	621.81 REMOVE & DISP. G.P.	604.40 CHANGE ELEVATION DI, CB OR MH	604.412 REHAB. DI, CB OR MH CLASS I									
LUDLOW			TON		LF	LF	LF	EA	EA	EA	EA	EA	LF	EA	EA	EA									
51+40	56+38	LT			525.0								525.0												ATTACH TO EXISTING GUARDRAIL ON TH 26 ANCHOR @ 56+38,
																									(INSTALL 1-16' RADIUS PANEL)
55+10	56+35	RT			125.0					2			127.0												ANCHOR @ 55+10, ANCHOR @ 56+35 (INSTALL 1-16' RADIUS PANEL @ EACH)
SHEET 1 SUBTOTAL			16.6		14789.0	225.0	0.0	38.0	0.0	5.0	4	4	13601.0	4		2	1								
SHEET 2 SUBTOTAL			0		103222.0	1987.5	130.0	30.0	2.0	16.0	4	4	13036.0	0		0	0								
SHEET 3 SUBTOTAL			0		650.0	0	0.0	0	0	2.0	0	0	652.0	0		0	0								
PROJECT SUBTOTAL			16.6		25763.0	2212.5	130.0	68.0	2.0	23.0	8	8	27289.0	4		2	1								
ROUNDING			3.4		339.0	37.5	5.0	0	0	0	0	0	211.0	0		0	0								
PROJECT TOTAL			20.0		26000.0	2250.0	135.0	68.0	2.0	23.0	8	8	27500.0	4		2	1								

ITEM DETAIL SHEET 3

SURVEYED BY CLD DATE 1/05
DRAWN BY NLL DATE 5/05
SQUAD LEADER CRB
DESIGN FILE NO. /pave/01b038/pb038.dgn
IPARM FILE pb038id03.i DATE PLOTTED 16-OCT-2009 16:4
PROJ. NAME CHESTER - LUDLOW
PROJ. NO. NH 2326(1)S
SHEET 13 OF 110 SHEETS