



TEMPORARY 4" WHITE LINE, PAINT			
DURABLE 4" WHITE LINE, THERMOPLASTIC			
STA	L 53+00	TO	L 54+71
	L 53+00	TO	L 64+00
	L 54+99	TO	L 64+00
			SOLID RT
			SOLID LT
			SOLID RT
TEMPORARY 4" YELLOW LINE, PAINT			
DURABLE 4" YELLOW LINE, THERMOPLASTIC			
STA	L 53+00	TO	L 54+60
	L 54+80	DOUBLE SOLID	RT (TH 19)
	L 55+00	TO	L 64+00
			SOLID LT & RT
TEMPORARY 24" STOP BAR, PAINT			
DURABLE 24" STOP BAR, THERMOPLASTIC			
STA	L 54+80	RT	(TH 19)
TEMPORARY LETTER OR SYMBOL, PAINT			
DURABLE LETTER OR SYMBOL, THERMOPLASTIC			
STA	L 54+90	RT	"STOP" (TH 19)

STEEL BEAM GUARDRAIL, GALVANIZED			
STA	L 53+00	TO	L 56+38
	L 55+10	TO	L 56+35
			LT
			RT
ANCHOR FOR STEEL BEAM RAIL			
STA	L 55+10	RT	
	L 56+35	RT	
	L 56+38	LT	
REMOVAL AND DISPOSAL OF GUARDRAIL			
STA	L 53+00	TO	L 56+42
	L 55+17	TO	L 56+44
			LT
			RT
REMOVING SIGNS			
AS SHOWN - 7			

ERECTING SALVAGED SIGNS
(NO FED. PART.)
AS SHOWN (TIS) - 4

LEGEND

R	=	REMOVE EXISTING
S	=	SALVAGE
R&S	=	REMOVE AND SALVAGE
N	=	NEW
RET	=	RETAIN
B-B	=	BACK TO BACK
—	=	NEW RAIL
—	=	EXISTING RAIL

PAVING PROJECT LAYOUT #55

PROJECT:	__CHESTER-LUDLOW	PROJECT NO.:	__NH_2326(I)S__
DESIGN FILE NAME:	Z:\pave\01b\038\pb038.dgn		
IPARM FILE NAME:	pb0381a55.1		
SURVEYED BY:	CLD_ENGINEERS, INC	SURVEY DATE:	01/05
SQUAD LEADER:	CRB	DRAWN BY:	MRS
CLD_04-0396		SHEET:	69 OF 110