STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #5

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																									
STA 360+40 RT	←	1	48	24	8.00						2			X 21		X																			E-152
STA 361+45 RT	→	1	48	24	8.00		1				2			X 22		X																			E-152
STA 369+60 RT	1030 1407 0700	1	6	10	0.42						1		X	8	X																			E-138
STA 373+61 LT	$500 FINE FOR THROWING TRASH ON HIGHWAYS AND STREAMS	1	24	30	5.00						1			X 14		X																			E-144
STA 376+80 LT	SHOULDER NARROWS	1	36	36	9.00						2			X 27		X																			E-151
STA 380+16 LT	1030 1407 0720	1	6	10	0.42						1		X	8	X																			E-138
STA 386+59 RT	LEGAL LOAD LIMIT 16,000 POUNDS	1	24	30	5.00						1			X 13		X																			E-141
STA 387+04 RT	BROOKS RD TH 93						1				1			X 13		X																		SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 1.0' FROM AND PERPENDICULAR TO TOP OF STOP SIGN.		
	STOP 1030 1407 0733	1 1	30 6	30 10	6.25 0.42																												BACK TO BACK		E-143 E-138
STA 387+05 RT	NO OUTLET	1	30	30	6.25						1			X 13		X																			106	
STA 388+27 RT	JCT	1	21	15	2.19						1			X 15		X																			E-136B
	TRUCK 10	1	24	24	4.00																														E-136B
STA 390+72 RT	1030 1407 0740	1	6	10	0.42						1		X	8	X																			E-138
												FT	FT ~~45~~	FT ~~165~~	FT ~~45~~	FT ~~165~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
	TOTALS		SF 55.37	SF	EA. + 2	EA						FT ~~210~~ 162			FT ~~210~~					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 5

PROJECT NAME: CHESTER-LUDLOW
PROJECT NUMBER: NH 2326(I)S
FILE NAME: /pave/Olb038/pb038.dgn PLOT DATE: 16-OCT-2009 17:19
PROJECT LEADER: CRB DRAWN BY: MRS
IPARM FILE NAME: pb038ts05.i CHECKED BY: NLL
CLD 04-0396 SHEET 83 OF 110