STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #7

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
														OPTION ITEMS																							
STA 400+00 LT	CHESTER 5	1	72	12	6.00						2			X 28		X																			E-123
	BELLOWS FALLS 18	1	72	12	6.00																														E-123
STA 400+19 RT	ONLY	1	30	30	6.25						1			X 14		X																			E-145A
STA 400+34 LT		1	24	30	5.00						1			X 13		X																			E-144
		1	18	18	2.25																												BACK TO BACK		E-150
		1	18	18	2.25																														E-150
STA 401+28 LT	1030 1407 0760	1	6	10	0.42						1		X	8	X																			E-138
STA 401+92 LT	SOUTH	1	24	12	2.00						1			X 15		X																			E-136B
	VERMONT 103	1	30	24	5.00																														E-136B
STA 402+13 RT	NORTH EAST	1	24	12	2.00						2			X 31		X																	X		E-136B
		1	24	12	2.00																														E-136B
	VERMONT 103 VERMONT 10	1	30	24	5.00																														E-136B
		1	24	24	4.00																														E-136B
		1	21	15	2.19																														E-136B
		1	21	15	2.19																														E-136B
	1030 1407 0762	1	6	10	0.42																														E-138

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

												FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB								
													~~15~~	~~105~~	~~15~~	~~105~~																				
TOTALS	SF 52.97	SF	EA.	EA		FT ~~120~~ 109			FT ~~120~~			LB			EA.	LB				EA.	EA.	LB													

TRAFFIC SIGN SUMMARY SHEET 7

PROJECT NAME: CHESTER-LUDLOW
PROJECT NUMBER: NH 2326(1)S
FILE NAME: /pave/01b038/pb038.dgn PLOT DATE: 16-OCT-2009 17:2
PROJECT LEADER: CRB DRAWN BY: MRS
IPARM FILE NAME: pb038ts07.i CHECKED BY: NLL
CLD 04-0396 SHEET 85 OF 110