STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #9

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
STA 410+86 LT	CHESTER 5 ↗	1	72	12	6.00						2			X 36		X																			E-123
	BELLOWS FALLS 18 ↗	1	72	12	6.00																														E-123
	← N. SPRINGFIELD 5	1	72	12	6.00																														E-123
	← SPRINGFIELD 8	1	72	12	6.00																														E-123
	H	1	24	24	4.00																														E-132
	←	1	24	6	1.00																														E-132
413+11 LT	SEE SHEET 34 FOR SIGNS	6			17.38									31																					
STA 413+25 RT	LUDLOW 8	1	72	12	6.00						2			X 28		X																			E-123
	RUTLAND 33	1	72	12	6.00																														E-123
STA 414+87 LT	⇅	1	36	36	9.00						2			X 27		X																			E-151
STA 415+25 RT	SPEED LIMIT 50	1	24	30	5.00						1			X 13		X																			E-142
STA 420+23 RT	↱	1	30	30	6.25						1			X 16		X																			E-151
STA 420+36 LT	JCT	1	21	15	2.19						1			X 14		X																			E-136B
	VERMONT 10	1	24	24	4.00																														E-136B
												FT	FT	FT ~~135~~	FT	FT ~~135~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF ~~67.44~~ 84.82	SF	EA.	EA						FT ~~135~~ 165		FT ~~135~~				LB			EA.		LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 9

PROJECT NAME: CHESTER-LUDLOW
PROJECT NUMBER: NH 2326(I)S
FILE NAME: /pave/Olb038/pb038.dgn PLOT DATE: 16-OCT-2009 17:2
PROJECT LEADER: CRB DRAWN BY: MRS
IPARM FILE NAME: pb038ts09.i CHECKED BY: NLL
CLD 04-0396 SHEET 87 OF 110