STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #10

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																									
STA 422+23 RT	TRUCKS ENTERING	1	36	36	9.00						2			X 31		X																				E-154
STA 422+40 LT	GASSETTS CHESTER DEPOT 4	1	30	18	3.75						1			X 14		X																				E-128A
	1030 1407 0800	1	6	10	0.42																															E-138
STA 427+15 RT		1	36	36	9.00						2			X 28		X																		106	
STA 432+96 RT	1030 1407 0820	1	6	10	0.42						1		X	8	X																				E-138
STA 434+90 RT		1	30	30	6.25						1			X 16		X																				E-151
STA 438+39 RT		1	24	30	5.00						1			X 14		X																		ASTM TYPE IX FLUORESCENT YELLOW SHEETING		E-150
STA 438+40 RT		1	24	30	5.00						1			X 14		X																		ASTM TYPE IX FLUORESCENT YELLOW SHEETING		E-150
STA 439+41 RT		1	24	30	5.00						1			X 14		X																		ASTM TYPE IX FLUORESCENT YELLOW SHEETING		E-150
STA 439+42 RT		1	24	30	5.00						1			X 14		X																		ASTM TYPE IX FLUORESCENT YELLOW SHEETING		E-150
STA 440+37 LT	TRUCKS ENTERING	1	36	36	9.00						2			X 28		X																				E-154
STA 440+46 RT		1	24	30	5.00						1			X 14		X																		ASTM TYPE IX FLUORESCENT YELLOW SHEETING		E-150
STA 440+47 RT		1	24	30	5.00						1			X 14		X																		ASTM TYPE IX FLUORESCENT YELLOW SHEETING		E-150
STA 441+52 RT		1	24	30	5.00						1			X 14		X																		ASTM TYPE IX FLUORESCENT YELLOW SHEETING		E-150
STA 441+53 RT		1	24	30	5.00						1			X 14		X																		ASTM TYPE IX FLUORESCENT YELLOW SHEETING		E-150
STA 443+19 LT		1	12	36	3.00						1			X 11		X																				E-107
STA 443+60 RT	BRIDGE 14 VT103	1	6	8	0.33						1		X	8	X																					E-134
												FT	FT ~~30~~	FT ~~255~~	FT ~~30~~	FT	FT ~~255~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS		SF 81.17	SF	EA.	EA							FT ~~285~~ 256				FT ~~285~~					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 10

PROJECT NAME: CHESTER-LUDLOW
PROJECT NUMBER: NH 2326(I)S
FILE NAME: /pave/01b038/pb038.dgn PLOT DATE: 16-OCT-2009 17:2
PROJECT LEADER: CRB DRAWN BY: MRS
IPARM FILE NAME: pb038tsl0.i CHECKED BY: NLL
CLD 04-0396 SHEET 88 OF 110