STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #18

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
STA C 120+89 LT	TRUCKS ENTERING	1	30	30	6.25						1			X 16		X																			E-154
STA C 123+04 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			X 14		X																			E-141
STA C 123+26 LT	GREVEN RD						1				1			X 14		X																	SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 1.0' FROM AND PERPENDICULAR TO TOP OF STOP SIGN.		
	STOP 1030 1406 0233	1 1	30 6	30 10	6.25 0.42																												BACK TO BACK		E-143 E-138
STA C 123+74 RT	GREVEN RD						+ 2				1			X 14		X																	SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 1.0' FROM AND PERPENDICULAR TO TOP OF STOP SIGN.		
	STOP 1030 1406 0234	1 1	30 6	30 10	6.25 0.42																												BACK TO BACK		E-143 E-138
STA C 123+95 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			X 14		X																			E-141
STA C 124+30 LT	NO OUTLET	1	30	30	6.25						1			X 15		X																	W14-2		
STA C 126+72 RT	1030 1406 0240	1	6	10	0.42						1		X	9	X																				E-138
STA C 127+99 LT		1	30	30	6.25						1			X 16		X																			E-155
STA C 131+25 RT	BRIDGE 21 VT103	1	6	8	0.33						1		X	8	X																				E-134
STA C 131+32 RT		1	12	36	3.00						1			X 11		X																			E-110
STA C 131+32 LT		1	12	36	3.00						1			X 11		X																			E-110
												FT	FT ~~30~~	FT ~~135~~	FT ~~30~~	FT ~~135~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
	TOTALS		SF 48.84	SF	EA. ~~2~~ 3	EA						FT ~~165~~ 142			FT ~~165~~					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 18

PROJECT NAME: CHESTER-LUDLOW
PROJECT NUMBER: NH 2326(1)S
FILE NAME: /pave/01b038/pb038.dgn PLOT DATE: 16-OCT-2009 17:2
PROJECT LEADER: CRB DRAWN BY: MRS
IPARM FILE NAME: pb038tsl8.i CHECKED BY: NLL
CLD 04-0396 SHEET 96 OF 110