QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

			GOV'T NON-PARTIC.	FULL E&C	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						3	3	EACH	THINNING AND TRIMMING FOR SIGNS	201.31	-
						100	100	CY	COMMON EXCAVATION	203.15	EST
						575	575	CY	EARTH BORROW	203.30	-
						12	12	CY	TRENCH EXCAVATION OF EARTH	204.20	0.3
						1	1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST
						69000	69000	SY	COLD PLANING BITUMINOUS PAVEMENT	210.10	2635.24
						12	12	CY	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.26	0.3
						13200	13200	TON	SUBBASE, RAP	301.40	116.50
						113000	113000	SY	RECLAIMED STABILIZED BASE	310.20	749
						125	125	TON	AGGREGATE SHOULDERS	402.12	-
						1700	1700	TON	AGGREGATE SHOULDERS, RAP	402.13	39
						800	800	CWT	EMULSIFIED ASPHALT	404.65	48.5
						1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	-
									*** BEGIN OPTION ITEMS AA ***		
						30000	30000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (0% RAP CONTENT)	490.30	610.03
						30000	30000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (0% < RAP CONTENT <15.0%)	490.30	610.03
						30000	30000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (15.0% ≤ RAP CONTENT < 25.0%)	490.30	610.03
						30000	30000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (25.0% ≤ RAP CONTENT ≤ 50.0%)	490.30	610.03
									*** END OPTION ITEMS AA ***		
						1	1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
						1	1	LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-
						1	1	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	-
						1	1	LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	-
					512		512	LF	BRIDGE EXPANSION JOINT, ASPHALT PLUG	516.10	-
					300		300	LF	REMOVAL OF EXISTING RAILING	525.10	-
					100		100	LF	BRIDGE RAILING REPAIR, TYPE I	525.50	-
					200		200	LF	BRIDGE RAILING REPAIR, TYPE II	525.55	-
					100		100	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	20
						1	1	EACH	PRECAST REINFORCED CONCRETE CATCH BASIN WITH IRON GRATE	604.20	-
						1	1	EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	-
						5	5	EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-
						5	5	EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	-
						4	4	EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS III	604.418	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS PAVEMENT
66364.76	SY	VT ROUTE 113
2635.24	SY	ROUNDING
69000	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
		WEARING COURSE
18,940.02	TON	TYPE IIS (MAINLINE)
9,866.95	TON	TYPE IVS (MAINLINE)
583.00	TON	TYPE IVS (SIDEROADS)
610.03	TON	ROUNDING
30,000	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: CHELSEA-VERSHIRE
PROJECT NUMBER: STP 2331(1)S

FILE NAME: 01c040.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: 01c040_10.i

PLOT DATE: 28-OCT-2011 13:35
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 10 OF 55