QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

			GOV'T NON-PARTIC.	FULL E&C	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
			3				3	EACH	CHANGE ELEVATION OF SEWER MANHOLES	604.42	-
						200	200	LF	6 INCH UNDERDRAIN PIPE	605.10	-
						250	250	HR	POWER GRADER RENTAL	608.15	EST
						675	675	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST
						180	180	HR	POWER BROOM RENTAL, TYPE I	608.30	EST
						90	90	HR	POWER BROOM RENTAL TYPE, II	608.31	EST
						1350	1350	HR	TRUCK RENTAL	608.37	EST
						250	250	HR	LOADER RENTAL, TYPE I	608.40	EST
						0.5	0.5	TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	EST
						2100	2100	CY	STONE FILL, TYPE I	613.10	31
						126	126	LF	TREATED TIMBER CURB	616.35	-
						13	13	TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	0.25
						25	25	EA	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	EST
						146	146	EACH	YIELDING MARKER POSTS	619.17	-
						14575	14575	LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	14.25
						2595.5	2595.5	LF	STEEL BEAM, GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205	-
						779	779	LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21	-
						22	22	EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50	-
						1	1	EACH	MANUFACTURED TERMINAL SECTION, TANGENT	621.51	-
						54	54	EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-
						12606	12606	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-
			3				3	EACH	ADJUST ELEVATION OF VALVE BOX	629.20	-
						850	850	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
						5000	5000	HR	FLAGGERS	630.15	EST
				1			1	LS	FIELD OFFICE, ENGINEERS	631.10	-
				1			1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
				1			1	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	-
						1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
						1	1	LS	TRAFFIC CONTROL	641.10	-
						3	3	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
						74000	74000	LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	160
						69000	69000	LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	735
						200	200	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	7
						59	59	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-
						148000	148000	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	320

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: CHELSEA-VERSHIRE
PROJECT NUMBER: STP 2331(1)S

FILE NAME: 01c040.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: 01c040_11.i

PLOT DATE: 28-OCT-2011 13:36
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 11 OF 55