STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 19

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																						SHS = FHWA STANDARD HIGHWAY BOOK		
STA. 182+30 RT VERSHIRE	VERSHIRE CENTER RD TH2 / STOP	1	30	30	6.25		1				1					X		X															MOUNT STREET SIGN OVER STOP SIGN		
	1130 0914 0345	1	6	10	0.42																												RI-1		SHS
																																	MOUNT REFERENCE PLAQUE BACK TO BACK WITH STOP SIGN		E-138
STA. 185+19 LT VERSHIRE	THE MOUNTAIN SCHOOL ← 2						1				2					X		X															MOUNT SALVAGED SIGN ON NEW POSTS		
	TSS SHEET 1 TOTAL				16.51		7								15	105																			
	TSS SHEET 2 TOTAL				0.84		8								30	105																			
	TSS SHEET 3 TOTAL				12.92		6									105																			
	TSS SHEET 4 TOTAL				17.42		4									120																			
	TSS SHEET 5 TOTAL				7.16		3								75	60																			
	TSS SHEET 6 TOTAL				2.16		2								90	30																			
	TSS SHEET 7 TOTAL				12.66		2								30	90																			
	TSS SHEET 8 TOTAL				8.41		3								60	60																			
	TSS SHEET 9 TOTAL				11.26		6									90																			
	TSS SHEET 10 TOTAL				22.85		2								60	90																			
	TSS SHEET 11 TOTAL				11.68		8								15	105																			
	TSS SHEET 12 TOTAL				9.42		13									165																			
	TSS SHEET 13 TOTAL				18.34		6									105																			
	TSS SHEET 14 TOTAL				0.84		9								30	150																			
	TSS SHEET 15 TOTAL				12.09		6								15	105																			
	TSS SHEET 16 TOTAL				24.00		3									150																			
	TSS SHEET 17 TOTAL				42.42		4									210																			
	TSS SHEET 18 TOTAL				42.92		1									150																			
	TSS SHEET 19 TOTAL				6.67		2									45																			
	SUBTOTAL				280.57							FT	FT	FT	FT	FT	FT	EA	LB	LB	LB		LB	LB	LB	LB								
	ROUNDING				4.43										420	2040																			
	TOTAL				SF 285.00	SF	EA. 95	SF				FT			FT 2460				LB	EA.	LB						EA.	EA.	LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

TRAFFIC SIGN SUMMARY SHEET 19

PROJECT NAME: CHELSEA-VERSHIRE
PROJECT NUMBER: STP 2331(1)S

FILE NAME: 01c040.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: 01c040_54.i

PLOT DATE: 28-OCT-2011 13:38
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 54 OF 55