COMPOSITE QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

STP 2334(I)			STP 2625(I)							
BRIDGE	FULL C.E.	ROADWAY	EMPLOYEE TRAINEESHIP	BRIDGE	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
		50				130	180	LF	HD STEEL BEAM GUARDRAIL, GALVANIZED/NESTED	621.216	
		28				46	74	EA	MANUFACTURED TERMINAL SECTION, FLARED	621.50	
		1				3	4	EA	MANUFACTURED TERMINAL SECTION, TANGENT	621.51	
						8	8	EA	TERMINAL CONNECTOR FOR STEEL BEAM GUARDRAIL	621.53	
		24				9	33	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	
						8	8	EA	GUARDRAIL APPROACH SECTION, GALVANIZED TYPE I	621.70	
		12,100				8550	20,650	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	
		1750				2350	4100	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
		2500				3500	6000	HR	FLAGGERS	630.15	EST.
	0.5				0.5		1	LS	FIELD OFFICE, ENGINEERS	631.10	
	0.5				0.5		1	LS	TESTING EQUIPMENT, CONCRETE	631.16	
	0.5				0.5		1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	
	3000				3000		6000	DL	FIELD OFFICE, TELEPHONE (N.A.B.I.)	631.26	
			520				520	HR	EMPLOYEE TRAINEESHIP	634.10	
		0.5				0.5	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	
		1					1	LS	TRAFFIC CONTROL (STP 2334(I))	641.10	
						1	1	LS	TRAFFIC CONTROL (STP 2625(I))	641.10	
		3				6	9	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	
		69,300				136,000	205,300	LF	DURABLE 4 INCH WHITE LINE, RECESSED POLYUREA	646.406	
		67,000				121,750	188,750	LF	DURABLE 4 INCH YELLOW LINE, RECESSED POLYUREA	646.416	
		20				60	80	LF	DURABLE 8 INCH WHITE LINE, RECESSED POLYUREA	646.446	
		70				220	290	LF	DURABLE 24 INCH STOP BAR, TYPE I TAPE	646.481	
		33				76	109	EA	DURABLE LETTER OR SYMBOL, TYPE I TAPE	646.491	
						50	50	LF	DURABLE CROSSWALK MARKING, TYPE I TAPE	646.501	6
		70,500				51,000	121,500	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	EST.
		68,250				35,500	104,750	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	EST.
		70				125	195	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	EST.
		46				44	90	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	EST.
						100	100	LF	TEMPORARY CROSSWALK MARKING, PAINT	646.702	EST.
		7000				9600	16,600	EA	LINE STRIPING TARGETS	646.76	EST.
		1880				550	2430	SY	GEOTEXTILE UNDER STONE FILL	649.31	EST.
		70				50	120	LB	SEED	651.15	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

COMPOSITE QUANTITY SHEET #2

PROJECT NAME: ARLINGTON & ARLINGTON-DORSET

PROJECT NUMBER: STP 2334(I) & STP 2625(I)

FILE NAME: 01C042.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p01c042quan2.i

PLOT DATE: 20-FEB-2013 16:39
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 4 OF 143