STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUNDATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
ARLINGTON: 34+19.0, RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X		X															SIGN ID CODE VR-017		E-141
	SPEED LIMIT 25	1	24	30	5.00	ALL SIGNS SIZES WERE INSTALLED PER PLAN. SEE LAYOUT SHEETS FOR LOCATIONS																												SIGN ID CODE R2-1		SHS
34+50.0, RT	River Rd	2	30	12	5.00						1					X		X															TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGNS ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST. SIGN ID CODE D3-1.	51	
	STOP 3130 0201 0065	1 1	30 6	30 10	6.25 0.42																											BACK-TO-BACK SIGN ID CODE R1-1 SIGN ID CODE VD-700		SHS E-138
42+24.0, RT	3130 0201 0080	1	6	10	0.42						1				X			X															SIGN ID CODE VD-700		E-138
52+80.0, LT	3130 0201 0100	1	6	10	0.42						1				X			X															SIGN ID CODE VD-700		E-138
63+36.0, RT	3130 0201 0120	1	6	10	0.42						1				X			X															SIGN ID CODE VD-700		E-138
64+20.0, RT		1	30	30	6.25						1					X		X															SIGN ID CODE W1-4L		SHS
	40 M.P.H.	1	18	18	2.25																												SIGN ID CODE W13-1		SHS
66+43.0, RT		1	48	24	8.00						2					X		X															SIGN ID CODE W1-6		SHS
												LF	LF	LF	LF 24	LF 70	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
TOTALS		SF 39.43	SF	EA.	SF							LF			LF 94					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #3

PROJECT NAME: ARLINGTON
PROJECT NUMBER: STP 2334(I)

FILE NAME: 01C042.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p01c042tss03.i

PLOT DATE: 20-FEB-2013 16:40
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 35 OF 143