STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 7

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUNDATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
ARLINGTON: I53+00.0, LT		1	30	30	6.25						2					X		X															SIGN ID CODE W2-2M		E-155
		1	36	8	2.00																													50	
I53+43.0, RT		1	36	36	9.00						2					X		X															SIGN ID CODE S3-1 SIGN SHALL BE FLUORESCENT YELLOW-GREEN.		SHS
					ALL SIGNS SIZES WERE INSTALLED PER PLAN. SEE LAYOUT SHEETS FOR LOCATIONS																																
I53+75.0, RT		1	6	8	0.33						1				X			X															SIGN ID CODE VD-701		E-134
I54+20.0, LT		1	6	8	0.33						1				X			X															SIGN ID CODE VD-701		E-134
I55+25.0, LT		1	24	30	5.00						1					X		X															SIGN ID CODE R2-1		SHS
I57+32.0, LT		2	48	12	8.00						1					X		X															TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGNS ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST. SIGN ID CODE D3-1.	51	
		1 1	30 6	30 10	6.25 0.42																												BACK-TO-BACK SIGN ID CODE R1-1 SIGN ID CODE VD-700		SHS E-138
I57+66.0, LT		1	24	30	5.00						1					X		X															SIGN ID CODE VR-017		E-141
I58+40.0, RT		1	30	30	6.25						1					X		X															SIGN ID CODE W11-8		SHS
		1	6	10	0.42																												SIGN ID CODE VD-700		E-138
												LF	LF	LF	LF 16	LF 112	LF		EA.	LB	LB	LB		LB 7.6	LB 9.0	LB 10.8	LB 14.6								
TOTALS		SF 49.25	SF	EA.	SF							LF			LF 128					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #7

PROJECT NAME: ARLINGTON
PROJECT NUMBER: STP 2334(I)

FILE NAME: 01C042.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p01c042tss07.i

PLOT DATE: 20-FEB-2013 16:40
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 39 OF 143