STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET 15

| MILEMARKER, STATION, OR SIGN NUMBER | SIGN LEGEND | SIGN DIMENSIONS | | | NEW & SALVAGED SIGNS | | | | EXIST POST | | NEW SIGN POSTS | | | | | | | | | | | | | | | | | | | REMARKS | SIGN DETAIL | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | EA | WIDTH (in) | HEIGHT (in) | "A" | "B" | SALV SIGN | SALV TIS | RETAIN | SALVAGE | NO. OF POSTS | FLANGED CHANNEL lb/ft | | | SQUARE STEEL (in) lb/ft | | | ANCHOR | SLEEVE | TUBULAR ALUMINUM Ø (in) lb/ft | | | FOUNDATION | TUBULAR STEEL Ø (in) lb/ft | | | | W-SHAPE STEEL FTG. SIZE | | WEIGHT | POST SIZE | SIGN FRAME REQUIRED | SHS = FHWA STANDARD HIGHWAY SIGNS BOOK | DETAIL ON DWG. NUMBER | STD. SHEET NUMBER |
| | | | | | | | | | | | | 1.12 | 2.0 | 3.0 | 1.88 | 2.42 | 3.35 | | | 1.3 | 1.7 | 1.7 | | 7.6 | 9.0 | 10.8 | 14.6 | 24" | 30" | | | | | | |
| ARLINGTON: 338+13.0, RT | RECREATION AREA | 1 | 30 | 30 | 6.25 | | | | | | 2 | | | | | X | | X | | | | | | | | | | | | | | |
| | HIDDEN DRIVE LEFT | 1 | 30 | 30 | 6.25 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | 3130 0201 0640 | 1 | 6 | 10 | 0.42 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | ALL SIGNS SIZES WERE INSTALLED PER PLAN, SEE LAYOUT SHEETS FOR LOCATIONS | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 339+62.0, RT | BRIDGE 5 VT313 | 1 | 6 | 8 | 0.33 | | | | | | 1 | | | | X | | | X | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 341+25.0, LT | BRIDGE 5 VT313 | 1 | 6 | 8 | 0.33 | | | | | | 1 | | | | X | | | X | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 342+68.0, RT | JCT | 1 | 21 | 15 | 2.19 | | | | | | 1 | | | | | X | | X | | | | | | | | | | | | | | |
| | VERMONT 7A | 1 | 24 | 24 | 4.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | BRIDGE 6 VT313 | 1 | 6 | 8 | 0.33 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 344+10.0, LT | BRIDGE 6 VT313 | 1 | 6 | 8 | 0.33 | | | | | | 1 | | | | X | | | X | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 345+65.0, RT | | 1 | 30 | 30 | 6.25 | | | | | | 1 | | | | | X | | X | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 347+43.0, RT | LEGAL LOAD LIMIT 24,000 POUNDS | 1 | 24 | 30 | 5.00 | | | | | | 1 | | | | | X | | X | | | | | | | | | | | | | | |
| | | | | | | | | | | | | LF | LF | LF | LF 24 | LF 70 | LF | | EA. | LB | LB | LB | | LB | LB | LB | LB | | | | | | |
| **TOTALS** | | SF 31.68 | SF | EA. | SF | | | | | | | LF | | | LF 94 | | | | | LB | | | EA. | LB | | | | EA. | EA. | LB | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

**TRAFFIC SIGN SUMMARY SHEET #15**

PROJECT NAME: ARLINGTON
PROJECT NUMBER: STP 2334(I)
FILE NAME: 01C042.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p01c042+ssl5.i
PLOT DATE: 20-FEB-2013 16:41
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 47 OF 143