STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 16

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUNDATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
ARLINGTON: 347+50.0, LT	WEST	1	24	12	2.00						1					X		X															SIGN ID CODE M3-4		E-136B
	VERMONT 313	1	30	24	5.00																												SIGN ID CODE MI-4		E-136B
					ALL SIGNS SIZES WERE INSTALLED PER PLAN. SEE LAYOUT SHEETS FOR LOCATIONS																																
347+78.0, RT	School st	2	36	12	6.00						1					X		X															TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGNS ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST. SIGN ID CODE D3-1	51	
	STOP 3130 0201 0658	1 1	30 6	30 10	6.25 0.42																												BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		SHS E-138
348+87.0, RT	EAST	1	24	12	2.00																												SIGN ID CODE M3-2		E-136B
	VERMONT 313	1	30	24	5.00																												SIGN ID CODE MI-4		E-136B
		1	21	15	2.19																												SIGN ID CODE M6-1		E-136B
348+94.0, LT	SPEED LIMIT 35	1	24	30	5.00						1					X		X															SIGN ID CODE R2-1		SHS
349+63.0, RT	← Manchester 9 Bennington 13 →	1 1	72 72	12 12	6.00 6.00						2												2	292.6								X	SIGN ID CODE DI-1 SIGN ID CODE DI-1	50 50	
	NORTH SOUTH	1 1	24 24	12 12	2.00 2.00																												SIGN ID CODE M3-1 SIGN ID CODE M3-3		E-136B E-136B
	HISTORIC HISTORIC	1 1	24 24	12 12	2.00 2.00																												SIGN ID CODE VM-478 SIGN ID CODE VM-478		E-136B E-136B
	VERMONT 7A VERMONT 7A	1 1	24 24	24 24	4.00 4.00																												SIGN ID CODE MI-4 SIGN ID CODE MI-4		E-136B E-136B
		1 1	21 21	15 15	2.19 2.19																												SIGN ID CODE M6-1 SIGN ID CODE M6-1		E-136B E-136B
	3130 0201 0660	1	6	10	0.42																												SIGN ID CODE VD-700		E-138
												LF	LF	LF	LF	LF 42	LF		EA.	LB	LB	LB		LB 292.6	LB	LB	LB								
TOTALS		SF 66.66	SF	EA.	SF							LF			LF 42					LB			EA. 2	LB 292.6				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #16

PROJECT NAME: ARLINGTON
PROJECT NUMBER: STP 2334(I)

FILE NAME: 01C042.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p01c042tssl6.i

PLOT DATE: 20-FEB-2013 16:41
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 48 OF 143