

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES

EMPLOYEE TRINEESHIP	BRIDGE	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
			1200	1200	CY	EARTH BORROW	203.30	50
			1	1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST.
			10,500	10,500	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	181
			500	500	TON	SUBBASE, RAP	301.40	EST.
			1800	1800	TON	AGGREGATE SHOULDERS	402.12	10
			430	430	CWT	EMULSIFIED ASPHALT	404.65	20
			1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	
			25,000	25,000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	292
			1	1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	
			1	1	LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	
			1	1	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	
			1	1	LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	
	320			320	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	5
	1			1	CY	REMOVAL OF CONCRETE OR MASONRY	529.25	0.8
	650			650	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	20
			26	26	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	EST.
			3	3	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	EST.
			3	3	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS III	604.418	EST.
			800	800	HR	POWER GRADER RENTAL	608.15	EST.
			160	160	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
			500	500	HR	POWER BROOM RENTAL, TYPE I	608.30	EST.
			50	50	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.
			400	400	HR	TRUCK RENTAL	608.37	EST.
			550	550	HR	LOADER RENTAL, TYPE I	608.40	EST.
			130	130	CY	STONE FILL, TYPE I	613.10	9
			110	110	EA	YIELDING MARKER POSTS	619.17	9
			7700	7700	LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	48.5
			200	200	LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21	
			130	130	LF	HD STEEL BEAM GUARDRAIL, GALVANIZED/NESTED	621.216	5.2
			46	46	EA	MANUFACTURED TERMINAL SECTION, FLARED	621.50	
			3	3	EA	MANUFACTURED TERMINAL SECTION, TANGENT	621.51	
			8	8	EA	TERMINAL CONNECTOR FOR STEEL BEAM GUARDRAIL	621.53	
			9	9	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	
			8	8	EA	GUARDRAIL APPROACH SECTION, GALVANIZED TYPE I	621.70	
			8550	8550	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	48
			2350	2350	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
			3500	3500	HR	FLAGGERS	630.15	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING, BITUMINOUS PAVEMENT
8066	SY	MAINLINE
1689	SY	BRIDGES
565	SY	SIDEROADS
181	SY	ROUNDING
10,500	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
16,882	TON	WEARING COURSE (TYPE IVS)
7066	TON	LEVELING COURSE (TYPE IVS)
247	TON	SIDE ROADS
513	TON	PULLOUTS
292	TON	ROUNDING
25,000	TON	TOTAL
		AGGREGATE SHOULDERS
1790	TON	SHOULDER BACKUPS
10	TON	ROUNDING
1800	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
------------	------	-------

QUANTITY SHEET #1

PROJECT NAME: ARLINGTON-DORSET

PROJECT NUMBER: STP 2625(1)

FILE NAME: p06c218.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: D.W.E.
IPARM FILE: p06c218quan1.i

PLOT DATE: \$DATE\$
DRAWN BY: C.A.K.
CHECKED BY: M.J.L.
SHEET 63 OF 143