QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

EMPLOYEE TRAINEESHIP	BRIDGE	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
		0.5		0.5	LS	FIELD OFFICE, ENGINEERS	631.10	
		0.5		0.5	LS	TESTING EQUIPMENT, CONCRETE	631.16	
		0.5		0.5	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	
		3000		3000	DL	FIELD OFFICE, TELEPHONE (N.A.B.I.)	631.26	
520				520	HR	EMPLOYEE TRAINEESHIP	634.10	
			0.5	0.5	LS	MOBILIZATION/DEMOBILIZATION	635.11	
			1	1	LS	TRAFFIC CONTROL (STP 2625(1))	641.10	
			6	6	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	
			136,000	136,000	LF	DURABLE 4 INCH WHITE LINE, RECESSED POLYUREA	646.406	622
			121,750	121,750	LF	DURABLE 4 INCH YELLOW LINE, RECESSED POLYUREA	646.416	459
			60	60	LF	DURABLE 8 INCH WHITE LINE, RECESSED POLYUREA	646.446	11
			220	220	LF	DURABLE 24 INCH STOP BAR, TYPE I TAPE	646.481	20
			76	76	EA	DURABLE LETTER OR SYMBOL, TYPE I TAPE	646.491	
			50	50	LF	DURABLE CROSSWALK MARKING, TYPE I TAPE	646.501	6
			51,000	51,000	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	EST.
			36,500	36,500	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	EST.
			125	125	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	EST.
			44	44	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	EST.
			100	100	LF	TEMPORARY CROSSWALK MARKING, PAINT	646.702	EST.
			9600	9600	EA	LINE STRIPING TARGETS	646.76	EST.
			550	550	SY	GEOTEXTILE UNDER STONE FILL	649.31	9
			50	50	LB	SEED	651.15	EST.
			400	400	LB	FERTILIZER	651.18	EST.
			1	1	TON	AGRICULTURAL LIMESTONE	651.20	EST.
			1	1	TON	HAY MULCH	651.25	EST.
			50	50	CY	TOPSOIL	651.35	EST.
			2400	2400	SY	TEMPORARY EROSION MATTING	653.20	17
			1200	1200	SF	TRAFFIC SIGNS, TYPE A	675.20	0.79
			150	150	LB	TUBULAR STEEL SIGN POST	675.33	1.8
			3000	3000	LF	SQUARE TUBE SIGN POSTS AND ANCHOR	675.341	48
			2	2	EA	FOUNDATION FOR TUBULAR STEEL SIGN POST	675.43	
			246	246	EA	REMOVING SIGNS	675.50	
			5	5	EA	ERECTING SALVAGED SIGNS	675.60	
			46	46	EA	DELINEATOR WITH STEEL POST	676.10	
			1	1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	
			200	200	LF	SPECIAL PROVISION (BRIDGE RAILING REPAIR, TYPE IV)	900.640	EST.
			3000	3000	SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	68

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

QUANTITY SHEET #2

PROJECT NAME: ARLINGTON-DORSET

PROJECT NUMBER: STP 2625(1)

FILE NAME: p06c218.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: D.W.E.
IPARM FILE: p06c218quan2.i

PLOT DATE: $DATE$
DRAWN BY: C.A.K.
CHECKED BY: M.J.L.